

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- THE LOTUS OIL CO. ET AL
Farm- Nuessen Bros. No. 1

SEC. 30 T. 21 R. 12E
NW NW NE
640' S of NL, 220' E
of WL

Total Depth. 1950 $\frac{1}{2}$ '
Comm. 3-31-55 Comp. 4-9-55
Shot or Treated.
Contractor. Geneva Oil & Gas Co.
Issued. 5-14-55

County Lyon

KANSAS



CASING:

8 $\frac{1}{4}$ " 22' cem.
4 $\frac{1}{2}$ " 1931' cem. Rec. 800' 4 $\frac{1}{2}$ "

Elevation. _____

Production. Dry

Figures indicate Bottom of Formations.

surface	9
lime	16
shale	19
lime	22
shale & lime	500
shale	580
lime	590
shale	600
lime	675
shale	844
lime	850
shale	904
lime	915
shale	1040
lime	1104
shale	1170
lime	1247
shale	1252
lime	1324
shale	1334
lime	1380
shale	1518
lime	1530
shale	1555
lime	1585
shale & lime	1625
lime	1630
shale	1640
lime & shale	1682
lime	1706
shale	1780
D. shale	1800
light shale	1820
sandy shale	1929
broken oil sand	1932
oil sand	1936 $\frac{1}{2}$
light sand	1950 $\frac{1}{2}$
Total Depth	

Tops: Scout
Bartlesville 1930

salt water at 1936
7 bailers water per hr. at 1941'
3 $\frac{1}{2}$ bbls. water per hr. at 1946'
Swabbed hole, made 175' water per hr.