


10-21-58

Total Depth. 2525'
 Comm. 5-22-57 Comp. 6-5-57
 Shot or Treated.
 Contractor. White & Ellis Drig., Inc.
 Issued. 5-3-58

County Marion
 KANSAS



Elevation. 1277' RB

Production. SWDW

CASING:

8 5/8" 204' w/125 sx cem.
 5 1/2" 2390' w/100 sx cem.

Figures indicate Bottom of Formations.

soil	5	sand	2456
clay	15	cherty lime	2466
sand	40	sdv lime	2525
gravel	45	Total Depth	
lime	70		
red rock	75		
lime	95	TOPS:	
shale	100	Kansas City	1572
lime	105	Mississippi chert	2119
shale	125	Misener	2258
lime	130	Hunton	2259
shale	135	Viola	2302
shale, shells	180	Simpson	2368
shale	200	Arbuckle	2385
shale, shells	350		
lime	370	TOPS: Scout	
shale, shells	740	Kinderhook	2132
lime	745	Maquoketa	2273
shale, rgh shells	836	Simpson sand	2379
lime, chalky	850		
shale, shells	897		
lime	920		
shale, lime strks	1020		
shale, shells	1056		
lime shale strks	1120		
lime	1180		
lime, shale strks	1240		
shale, shells	1275		
shale, lime strks	1300		
lime	1340		
shale, lime strks	1457		
shale, shells	1497		
lime	1517		
shale, shells	1572		
lime	1612		
lime, shale stks	1677		
lime	1788		
brwn lime(no odor)	1812		
lime	1922		
shale, lime shells	1975		
lime	1979		
shale lime stks	2052		
lime	2057		
shale, lime	2119		
shale	2258		
sand	2259		
dolomite	2274		
shale	2302		
lime	2368		
sand	2385		
lime	2408		

lime, sand, shale	2412
shale	2423
sdv shale	2426
sand	2440
lime	2448
sdv lime	2451

Cable Tool

Buckeye Supply Co.

Casing Record
 8 5/8" 204' cemented
 w/125 sacks
 5 1/2" 2390' cemented w/
 100 sacks
 T.D. 2525

Location: SE NW SW

Sec. 10-21-5E

Marion County, Kansas

Farm: Ernest Lalouette #2 (SWD)

Well Owner: White & Ellis Drilling, Inc.

Contractor: White & Ellis Drilling, Inc.

Started: Spudded 5-22-57

Undersurface 6-5-57

Completed: 6-25-57

Kelly bushing measurements 5' above ground level.

Formation

Depth- Figures indicate bottom of formation

Soil	0-5	Lime HD	1922
Clay	15	Grey Shale & Lime Shells	1975
Sand	40	Lime	1979
Gravel	45	Shale Lime Strks.	2052
Lime	70	Lime, Rough	2057
Red Rock	75	Shale & Lime	2119
Lime	95		
Shale	100	Mississippi Chert	
Lime	105		
Shale	125	Shale	2258
Lime	130	Top of Misener	
Shale	135	Sand	2259
Shale & Shells	180	Top of Hunton	
Shale	200	Dolomite	2274
Shale & Shells	350	Shale	2302
Lime	370	Top of Viola	
Shale & Shell	710	Lime	2368
Lime	715	Top of Simpson	
Shale, Rough Shells	876	Sand	2385
Lime, Cherty	880	Top of Arbuckle	
Shale & Shells	897	Lime	2408
Lime	920		
Shale Lime Strks.	1020	Cable Tools	
Shale & shells	1056		
Lime Shale Strks.	1120	Lime, sand & Shale	2412
Lime	1180	Shale	2433
Lime Black Shale Strks.	1240	Sandy Shale	2426
Shale & Shells	1275	Sand	2440
Shale & Lime Strks.	1300	Lime	2448
Lime	1340	Sandy Lime	2451
Shale & Lime Strks.	1457	Sand, Hard	2456
Shale & Shells	1497	Cherty Lime	2466
Lime	1517	Sandy Lime	2525
Shale & Shells	1572		

Top of Kansas City

Lime	1612
Lime & Shale Strks.	1677
Lime	1788
Brown Lime (no order)	1812

State Geological Survey
 WICHITA, BRANCH

MAY 23 1977