


Company. WHITE & ELLIS DRILG., INC.
Farm- WANER No. 1

SEC. 9 T. 21 R. 21
NE SW SE
1220' fr SL 3630' fr WL SE
9-21-5 E
County Marion KANSAS

Total Depth. 2268'
Comm. 3-14-57 Comp. 3-18-57
Shot or Treated.
Contractor. White & Ellis Drilg., Inc.
Issued. 4-13-57



Elevation. ??

Production. Dry

CASING:
8 5/8" 103' w/100 sx cem.

Figures indicate Bottom of Formations.

K.B. Meas. 5' above G.L.
soil 4
shale 18
wtr sand 25
lime 50
shale-shells 62
lime 90
lime-shale strks 103
shale-shells 112
lime 128
lime-shale strks 243
shale-lime strks 420
lime 460
shale-shells 590
lime-shale strks 698
shale-lime strks 708
shale-shells 890
lime-shale strks 1072
lime 1143
lime-shale strks 1208
shale-shells 1260
lime HD rgh strks 1296
lime shale strks 1310
lime 1386
shale-shells 1403
shale-lime strks 1438
sand no odor 1452
shale-shells lime strks 1490
lime 1790
lime-chat 1797
lime 1855
shale-shells 1869
lime w/shale strks 1914
shale-shells 1964
shale-lime strks 1996
shale-shells 2011
lime 2022
lime-shale strks 2075
shale-shellstr c 2090
lime 2131
shale 2213
lime 2220
shale 2258
lime 2268
Total Depth

TOPS:
Mississippi 2090
Kinderhook 2131
Horton 2213 *Denton 2213*