

21580 Duplicate

Lease Rogler

Well No. 1 S 32 T 21S R 8E.

Company (M. Green)

County,

State Kansas Elev.

Location 1020 n of S line, 300 w of E line

Dr. Commenced

Dr. Completed.

Drilled by.

Initial Prod.

15 1/2 80

Casing Record.

12 1/2 — 913'4"

10 - 1369

8 2130

6 5/8 2473

5 3/16 2890

- Sand black soft 3
- sand yellow soft 28
- Lime light hard ~~25~~ 55
- Slate brown soft 65
- Lime light hard 80 75 80'
- Slate blue soft 86
- Lime yellow hard 91
- Slate white soft 101
- Slate blue soft 105
- Slate white soft 120
- Lime white hard 125
- Slate white soft 155
- Lime white hard 175
- Slate white soft 190
- slate blue soft 210
- Lime light hard 217
- Slate white soft 252
- Lime white hard 257
- Slate white soft 287
- Slate blue soft 295
- Slate blue soft 308
- Redrock soft 313
- Slate white soft 323
- Lime white hard 328
- Slate white soft 338
- Slate blue soft 360
- Sand light soft 370 2 B. H2O
- sand slate dark soft 380

Slate black soft	430	
Lime white hard	440	
Lime hard light	450	
Slate white soft	460	
Slate blue soft	490	
Lime light hard	510	
Slate dark soft	520	
Lime light hard	524	
Slate blue soft	529	
Slate brown soft	534	
Slate blue soft	555	
Lime light hard	575	
Slate dark soft	615	
Slate blue soft	625	
Sandy slate brown soft	630	
shale blue soft	635	
shale brown soft	655	
Slate white soft	665	
Mud yellow soft	670	
slate blue soft	695	
slate brown soft	700	
Lime yellow hard	715	
slate blue soft	720	
slate white soft	730	
slate blue soft	770	
slate white soft	790	
Lime white hard	820	
slate white soft	830	
Lime white hard	835	
Slate white soft	880	
Slate blue soft	890	
Lime light hard	900	12½ 913½
Slate white soft	914	
Lime light hard	929	
Slate black soft	924	
Lime light hard	949	
Slate white soft	969	
Lime light hard	979	
Slate white soft	990	
Lime white hard	1030	
Lime and slate dark med	1060	
Sand light sft	1070	
Slate white soft	1100	
Lime white hard	1130	
Lime yellow hard	1210	
Slate white soft	1280	
Sand light soft	1305	HFW
Slate white soft	1375	
Lime light hard	1380	

Rogler #1.

32 21S SE.

Slate dark soft	1500
Lime light hard	1550
Slate dark soft	1560
Sandy lime soft	1615
Slate dark soft	1720
Lime light hard	1730
Sand light soft	1735 HFW
Lime light hard	1914
Slate dark soft	2004 8" 1807
Slate white soft	2020
Sand light soft	2055 HFW
Lime light hard	2080
Slate lime soft	2130 U. R. 8" 2065
shale	2144
lime	2194
shale white	2245
lime	2255
shale	2300 6" 2310
shale	2320
Shale	2420
shale black	2465
lime white hard	2475 Top Miss.
lime white hard	2680 HFW 2550
	→ 2810
Shale Black	2927
Sand Brown Soft	2930 (Water)
Lime sandy white hd	2941
Shale blue soft	2960
Lime Brown soft	2970 (Water)
Sandy lime white hard	3010 T.D.