

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


25-21-9E

Company- GLEN DRESSLER et al
Farm- Hedlund No. 1

SEC. 25 T. 21 R. 9E
SE SE NE
3290' N of SL 5030' W of EL

Total Depth. 2272 PBTD 2262
Comm. 4-27-57 Comp. 5-20-57
Shot or Treated.
Contractor. Sauder Drilling Co.
Issued. 7-13-57

County Chase
KANSAS



12 1/2" casing pulled 6 1/4" 36' cmt. Elevation. 1332
10 in. 1128' pulled 4 1/2" 2266' w/ 995 sx cmt.
8 in. 1602' pulled
7 in. 1918' pulled
Production. 25 BOPD

Figures indicate Bottom of Formations.

clay	15	lime	1110
shale	20	shale	1210
shells	25	lime	1220
shale	65	shale	1235
lime	75	lime	1250
shale	107	shale	1300
red rock	112	lime	1305
shale	120	shale	1335
lime	125	lime, 3 BW 1365-70	1430
shale	167	shale	1510
red rock	175	lime, HFW 1540-50	1588
shale	200	shale	1600
lime	205	lime	1610
shale	225	shale	1620
lime	230	lime, 2 BW 1680-90	1755
shale	325	shale	1860
shells	345	lime	1870
shale	375	shale	1880
lime	385	lime	1885
shale	390	shale	1890
lime	395	lime	1910
shale	410	shale	1950
lime	415	lime	1970
shale	425	shale	1985
lime	440	lime	1990
shale	450	shale	2000
lime	455	lime	2005
shells	465	shale	2145
shale	525	broken sand, sl. oil odor	2155
lime	538	shale	2224
shale	590	sandy shale	2231
lime	610	gray dry sand	2242
shale	670	black shale	2249
lime	675	broken sand	2255
shale	680	good brown sand, 10 GOPH	2261
lime	715	sandy shale	2264
shale	735	gray sand, oil inc 16 GOPH	2272
lime	745	Total Depth	
shale	765	Plugged back to	2262
shells	785		
shale	805	TOPS:	
lime	815	Bartlesville	2255
shale	830		
lime	850	PB to 2266 Sand fracked w/ 27,000#	
shale	855	sand & 850 bbls wtr. @ 1400#. PB	
lime	875	to 2262 & Perf. 2257-60, sand frac	
shale	895	w/ 25,000# sand & 800 bbls wtr. @	
lime	903	700#	
shale	960		
lime	970		
shale	985		
lime	1010		
shale	1030		
lime	1040		
shale	1090		
sand, 10 BW	1100		
shale	1105		