

6-22-10E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- Atyeo "C" No. 26-W

SEC. 6 T. 22 R. 10E
CWL NW SE
660' S & 25' E of Center

Total Depth. 2282'
Comm. 5-4-55 Comp. 5-8-55
Shot or Treated.
Contractor. White & Ellis Drlg. Co.
Issued. 3-24-56

County Greenwood
KANSAS



Elevation. 1350' RTB

Production. Water Input

Figures Indicate Bottom of Formations.

CASING:
8 5/8" 64.19' cem w/40 sx
5 1/2" 2230' cem w/125 sx

Steel Line Measurement:
519' = 519'
1514' = 1514'

clay	7
shale & lime strks	40
lime, hd. & rough	44
broken lime	54
shale & shells	205
lime	226
shale & shells, r. strks	368
shale & lime strks	448
shale & shells	520
lime, hd.	530
shale & shells	682
lime, hd.	720
shale & shells	728
lime, hd.	737
shale & shells	800
lime, hd.	806
shale & lime strks	908
shale & shells	970
lime	1000
shale, rough shells	1137
shale & shells	1210
Douglas sec.	1307
Top. Lans.	1368
lime, hd.	1401
broken lime, w/shale strks	1421
shale & shells	1480
gray shale	1538
shale & shells	1567
lime, hd.	1583
lime, hd. strks	1615
lime, hd.	1632
lime, hd. strks	1675
lime	1757
shale & shells	1947
lime	1953
shale & shells	1974
shale & hd. lime strks	2010
shale & hd. shells	2092
gry. sdy. shale w/shells	2159
black coal or shale	2161
gray shale, sdy.	2206
coal or dk. shale	2225

Core #1	2282
Total Depth	
Tops:	
Lansing Ls.	1306
Base Lansing	1422 No oil noted.
Kansas City Ls.	1537
Base Kansas City	1742 No oil noted.
Bartlesville Sd.	2242 1/2

Best Bartlesville Pay:
Core # 1 2231-82' (51') Rec. 51'

All measurements from RTB.