


14-22-11E

10" 959 FARM Fromm NO. 10 COUNTY
 20" 8 1-4 1520 COMPANY Empire Gas & Fuel Co.
 15 1-2 6 5-8 1871 CONTRACTOR
 12 1-25 12 5 3-16 COMMENCED 6-18-26 COMPLETED 7-7-26.

Greenwood



TOTAL DEPTH 1905' SHOT 100 QUARTS BETWEEN 1883-1905'.

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Empire Gas & Fuel Co.,
 Oil Hill, Kansas.

ELEVATION

INITIAL PRODUCTION 130 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS.
REMARKS

Formation	Depth	Formation	Depth
soil	5	shale	645
slate	40	lime	650
lime	60	shale	655
shale	90	lime	665
lime	95	slate	800
shale	120	lime	805
lime	130	shale (HFW 820')	820
shale	185	water sand	885
lime	195	sandy shale	930
shale	200	lime	935
lime	220	shale	955
slate	270	lime	965
lime	275	slate	970
shale	280	lime	1090
lime	315	slate	1215
slate	355	lime	1230
lime (3 B.W. 360')	365	slate (1 BW 1260')	1235
shale	375	lime (6 BW 1295')	1340
lime	385	shale	1345
shale	390	lime	1395
lime	395	shale	1505
shale	410	lime	1510
lime	430	slate	1520
shale	440	lime	1540
lime	460	shale	1580
slate	465	sand (1 B.W.)	1585
lime	475	shale	1595
shale	505	lime	1600
lime	520	shale	1862
shale	525	sandy shale	1871
lime	530	shaley sand	1877
shale	545	sand	1905
lime	550		
slate	570	1st oil	1884
lime	580	Best pay	1892-1905
slate	595		
lime	625		
slate	630		
lime	635		