


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,  
Wichita, Kansas

14-22-11E  
SEC. 14 T. 22 R. 11E  
SW SE SE

Company- A. R. JONES & PAT MICHAELIS  
Farm- Sites No. 1

County Greenwood  
KANSAS



Total Depth. 1859'  
Comm. 10-10-56 Comp. 10-15-56  
Shot or Treated. Fractured w/7500#'s sand  
Contractor. Geneva Oil & Gas Company  
Issued. 12-8-56

Elevation. ?

Production. 25 BOPD & 125 bbls  
water

CASING:

8 5/8" @80' w/cem  
4 1/2" @1834' w/cem.

Figures Indicate Bottom of Formations.

|                    |      |
|--------------------|------|
| soil               | 5    |
| lime               | 8    |
| shale              | 14   |
| lime               | 27   |
| shale              | 35   |
| lime               | 45   |
| shale              | 80   |
| shale & shells     | 110  |
| shale              | 170  |
| shale & lime       | 557  |
| lime               | 576  |
| shale              | 590  |
| lime               | 600  |
| shale              | 780  |
| lime               | 785  |
| shale              | 830  |
| sand               | 845  |
| shale              | 865  |
| sand               | 870  |
| shale              | 913  |
| lime               | 919  |
| shale              | 930  |
| lime               | 1050 |
| shale              | 1070 |
| lime               | 1080 |
| shale              | 1179 |
| shale & shells     | 1195 |
| lime               | 1215 |
| sandy lime         | 1225 |
| lime               | 1370 |
| shale              | 1540 |
| lime               | 1560 |
| shale              | 1685 |
| sandy shale        | 1730 |
| shale              | 1832 |
| Rotary Total Depth | 1834 |
| oil sand           | 1842 |
| 100% saturation    |      |
| light, fine sand   | 1852 |
| 10% saturation     |      |
| dark sand          | 1857 |
| No saturation      |      |
| dark sand          | 1859 |
| Total Depth        |      |

SCOUT TOPS  
Lansing 925  
Bartlesville 1832