

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


14-22-11E

Company- CITIES SERVICE OIL CO.
Farm- Madison Unit "E" No. 36

SEC. 14 T. 22 R. 11E
NE NW NW
840' E & 250' S of NW cor.

Total Depth. 1936'
Comm. 1-28-58 Comp. 2-1-58
Shot or Treated.
Contractor. White & Ellis Drlg., Inc.
Issued. 8-9-58

County Greenwood
KANSAS



Elevation. 1212' RB (4' above DL)

Production. 68 BO - 219 BWPD
(after frac)

CASING:

10 3/4" 104' w/80 sx cem.
7" 1935' w/125 sx cem.

Figures Indicate Bottom of Formations.

All Meas. fr RB.	
soil	6
clay	15
lime	40
shale, shell	80
shale	100
lime	106 1/2
shale, lime stks	190
lime, shale	337
shale, red rock	395
lime, shale	480
shale, lime stks	605
lime	690
shale	795
shale, lime	802
sand	969
lime	1097
shale	1216
lime	1396
shale, sand	1445
shale, lime	1545
lime	1561
shale w/lime stks	1680
sdv shale	1795
sdv shale w/sd. stks	1865
shy. sand	1871
Core #1	1896
Cor3 #2	1921
shale	1936
Total Depth	

Core #1 1871-1896' (25')
Rec. 25 1/2'
Core #2 1896-1921' (25')
Rec. 22'

Steel Line Meas.	S. H. S.
575' = 575'	575' O.K.
1020' = 1020'	1020' O.K.

Top Douglas Sd. 816
Base 970 N.S.O.

Top Lansing Ls. 970
Base 1097 N.S.O.

Top Kansas City Ls.	1223
Base	1403 N.S.O.
Top Marmaton	1519
Base	1678 N.S.O.
Top Cherokee	1678
Top Bartlesville Zone	1863
Top Bartlesville sand	1868
T.	48
Base	1916

Best Pay: 1868-1910'
Ran Schlumberger log.
This well was not shot.