


WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION 330' fr NL 986.3' fr EL E/2 NE/4 SEC 11T 22 R 10E

10" 1150 FARM M. J. Green NO. 3 COUNTY Greenwood
20" 8 1-4 1715 COMPANY Phillips Petroleum Company.
15 1-2 6 5-8 2046 CONTRACTOR
12 1-2 631 5 3-16 COMMENCED 9/1/26. COMPLETED 9.19.26



SHOT 220 QUARTS BETWEEN 2091-2140'
CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Phillips Petroleum
Company, Bartlesville, Oklahoma.

FIGURES INDICATE BOTTOM OF FORMATIONS.

ELEVATION
INITIAL PRODUCTION 180 bbls.
after shot.

REMARKS 10/23/26.

Formation	Depth	Formation	Depth
lime white hrd	5	shale dark soft	980
shale dark soft	60	lime white hrd	985
lime white hrd	65	shale black soft	1000
shale white soft	100	lime white hrd	1005
lime white hrd	105	shale dark soft	1065
shale dark soft	160	lime white hrd (7 BW 1070')	1070
shale dark soft	165	water sand white soft	1080
lime dark hrd	175	lime white hrd	1155
shale dark soft	200	lime white hrd	1170
shale dark soft	225	lime white hrd	1235
lime white hrd	245	shale black soft	1290
shale white sft	280	shale white soft	1300
shale black sft	330	shale white sft (10" 1155')	1360
shale black sft	345	lime white hrd	1370
shale black sft	370	shale dark sft	1380
lime white hrd	375	lime white hrd	1390
shale drk sft	385	lime white hrd	1440
shale drk sft	425	lime white hrd	1490
lime white hrd	430	lime white hrd	1560
shale white sft	480	lime white hrd	1590
lime white hrd	500	shale black sft	1630
shale drk sft	505	shale black sft	1690
lime white hrd	520	lime white hrd	1700
shale drk sft	530	shale white sft (Set 8 1/4"*)	1715
lime white hrd	555	lime white hrd	1720
shale white sft	575	shale black soft	1740
lime white hrd	585	shale white soft	1765
shale black sft	630	lime white hrd	1770
lime white hrd (12 1/2" 630')	635	shale white soft	1790
shale drk sft	655	lime white hrd	1800
lime white hrd	665	shale drk sft	1875
shale white sft	675	shale drk sft	1900
lime white hrd	700	lime white hrd	1905
shale black soft	710	shale white soft	1930
lime white hrd	735	lime white hrd	1935
shale white soft	745	shale drk sft	1980
lime white hrd	760	shale black soft	2042
shale drk soft	780	(6 5/8" at 2048')	
lime white hrd	800	sand shale brown soft	2069
shale white soft	805	oil sand brown sft	2143
lime white hrd	820	Total Depth	2143
lime white hrd	850		
shale black soft	855		
lime white hrd	890		
shale dark soft	940		
lime white hrd	950		

SAND RECORD

Top of sand 2048, top pay sand
2048, first oil 2048 break from
2069-2080 Top second oil 2080
bottom oil sand 2140 total depth 2143
present total depth 2143. Sand brown
soft.