

20'	10"
15 1-2	8 1-4
12 1-2	6 5-8
	5 3-16


FARM Young NO. 1 COUNTY Greenwood

COMPANY Shaffer & Howell Drilling Co.

CONTRACTOR Shaffer & Howell

COMMENCED April 24, 1926.

COMPLETED May 28, 1926.



TOTAL DEPTH 1975'

SHOT QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO
 Drilling Company, Wichita, Kansas.

Shaffer, Howell
 ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION Dry.

REMARKS 11/6/26.

Formation	Depth	Formation	Depth
gumbo yellow soft	5	lime white hrd	1200
lime white hrd	8	shale dark soft	1335
shale white soft	43	lime white hrd	1340
lime white hrd	125	shale dark soft	1355
shale blue soft	140	lime white hrd	1375
lime white hrd	145	shale dark soft	1395
shale white soft	170	sand white soft	1405
lime white hrd	185	shale dark soft	1425
shale blue soft	190	lime white hrd	1435
lime white hrd	225	shale dark soft	1447
slate blue soft	245	(1355' 8" csg.)	
lime white hrd	265	lime white hrd	1470
slate blue soft	268	shale dark soft	1530
sand white soft	273	sand white soft (2 BW 1535')	1545
lime white hrd	283	slate dark soft	1580
shale dark soft	303	lime white hrd	1585
lime white hrd	313	slate sandy white soft HFW	1690
shale white soft	323	sand white soft (1723')	1775
lime dark hrd	328	slate black soft	1850
shale white soft	370	(very cavey)	
lime white hrd	385	lime white hrd (Top lime)	1930
shale dark soft	407	(1850' 6 5/8" csg.)	
lime white hrd	475	slate blue soft	1940
shale dark soft	530	lime white hrd (HFW 1975')	1970
sand white soft	565		
shale dark soft	670	TOTAL DEPTH	1975'
lime white hrd	685		
sand white soft	705		
(H. F. W. 700')			
slate dark soft	725		
sand white soft	748		
shale dark soft	771		
lime white hrd	795		
(776' 12 1/2" casing)			
slate white soft	807		
lime white hrd	875		
(1 B. W. 870')			
slate dark soft	973		
lime white hrd	1030		
shale dark soft	1038		
(1040' 10" casing)			
lime white hrd	1045		
(1 B. W. 1045')			
slate white soft	1065		
lime white hrd	1115		
sand white soft	1120		
(1 B. W. 1120')			