

20' 10'
15 1-2 8 1-4
12 1-2 6 5-8
5 9-16

FARM Jeanette
COMPANY C. E. Hano & S. L. Lamar
CONTRACTOR
COMMENCED

NO. 1 COUNTY Greenwood

COMPLETED April 21, 26.



TOTAL DEPTH 1847'

SHOT

QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

ELEVATION

INITIAL PRODUCTION *D + abd.*

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS

Formation	Depth	Formation	Depth
soil & broken lime	45	shale	1110
hard gray lime	55	lime (Oswego)	1260
blue mud	90	slate	1465
slate & hard shells	130	lime	1480
gray lime	200	slate	1505
blue sticky mud	230	lime with small break	1525
white lime	240	shale	1540
white shale	250	sandy lime	1565
lime	255	shale	1595
white shale	270	sand (HFW)	1620
lime	275	(Set 6 5/8" casing 1622')	
hard shale	290	slate	1640
hard gray lime	300	lime	1650
shale	320	slate	1695
hard gray lime	327	sandy lime	1710
blue shale	350	dark sandy slate	1743
red rock	355	Bartlesville sand	1761
white shale	470	dark sandy shale	1840
(Set 10" casing -412')		slate cave	1847
lime	490		
blue shale	500		
white shale	530		
lime shale	550		
blue shale (HFW 710')	705		
white sand	780		
light shale	835		
hard dark lime	840		
slate	850		
lime	860		
slate	885		
lime (Big lime)	970		
(Set 8 1/4" casing 900')			
shale	1000		
lime & slate breaks	1095		
		TOTAL DEPTH	1847'