


WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY  
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION NE NW NW  
330' fr NL 330' fr EL

SEC 12 T 22 R 10 E.

10" 1086 FARM J. B. Fechter NO. 2 COUNTY Greenwood  
20" 8 1-4 1686 COMPANY The Prairie Oil & Gas Co.  
15 1-2 29 6 5-8 1984 CONTRACTOR J. J. Muth.  
12 1-2 301 5 3-16 1987 COMMENCED May 3, 1926. COMPLETED May 23, 1926.



TOTAL DEPTH SHOT QUARTS BETWEEN  
CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO The Prairie Oil & Gas  
Co., Independence, Kansas. ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 200 bbls,

REMARKS

Formation	Depth
soil	16
gravel (HFW)	30
lime	50
slate black	100
(Set 29' 15 $\frac{1}{2}$ " csg.)	
lime	150
slate white	190
lime	220
slate white (Set 301-6-12 $\frac{1}{2}$ " csg)	300
lime	325
slate	375
lime	390
white slate	400
slate	425
lime	455
slate	475
lime	500
slate	520
lime	540
slate hrd	560
lime white hard	595
slate white	605
lime white hrd	630
slate white	685
lime hard	720
slate	730
lime hard	760
slate black	930
lime	950
slate black (HFW 1030')	1015
lime hard	1050
slate	1055
lime	1070
slate (Set 1086-6)	1080
lime (10" csg.)	1220
slate	1330
Oswego lime (2 B. W.)	1600
shale (pr. hr 1195')	1644
lime	1669
slate (Set 1686-6 8 $\frac{1}{2}$ " csg.)	1700
lime	1720
slate	1750
lime	1770
slate	1887
lime (correcting SLM 1959')	1907
slate	1954
sand dark	1966
shale dark soft	1984
(Set 1959 6 5/8" csg.)	
Oil sand gray med.	2069
(Reamed to 1984')	

Light show of oil 1984 first by  
sand 2002 oil. Filled up to  
500' while drilling.