


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company—CITIES SERVICE OIL CO.
Farm—Schwab No. 59

SEC. 30 T. 22 R. 13E
NE SW NW
1360' S & 700' E of NWc

Total Depth. 1752 PBTB 1726
Comm. 4-17-55 Comp. 4-21-55
Shot or Treated. shot 90 qts. OWE 1690-1726
Contractor. White & Ellis Drilling Co.
Issued. 7-30-55

County Greenwood
KANSAS



CASING:
8 5/8 @ 65.65' w/ 40 sx cmt.
5 1/2 @ 1679' w/ 125 sx cmt.

Elevation. 1121 RB

Production. 11 BO, 110 BW

Figures indicate Bottom of Formations.

soil	4	core #1 1681-1729 (48') rec 48'
shale	18	core #2: 1729-41, (12') rec. 10 1/2'
lime	24	
broken lime	30	All RB Meas.
shale & shells	40	
lime	45	SLM 518 OK, 1024 OK, 1515 OK, 1606 OK
shale & shells	47	
lime	52	
shale & lime streaks	61	MICT. DD 1741-52, 800' WIH could not bail down, PB to 1726, swb. tr. oil & 41 BW/16 hrs. swb. tr. oil & 32 BW/16 hrs. shot well, CO to 1726 tr. oil & 1505' wtr. in hole/8 hrs. swb. 6 BO, 9 BW/16 hrs. 950' fluid, swb. 9 BW, CO to 1721
lime	65	
shale & lime streaks	70	
lime	90	
lime & shale streaks	112	
shale & shells	125	
shale & lime streaks	190	
lime	235	
shale & shells	250	
lime	290	
shale & lime streaks	370	
lime	403	
shale & shells	619	
shale & sand streaks	738	
Lansing lime	753	
lime & shale streaks	822	
lime & sand	930	
brown lime	959	
lime, base of Lansing	960	
lime & shale streaks	1126	
lime	1160	
lime & shale streaks	1173	
shale & shells	1242	
shale	1312	
shale & lime streaks	1325	
lime	1337	
lime & shale streaks	1423	
shale & brown lime streaks	1470	
sandy shale	1550	
sandy shale & shells	1566	
sandy shale	1601	
shale & shells	1677	
shale & sand streaks	1696	
sand	1732	
shale & sand streaks	1734	
shale	1752	
Total Depth		

Log

TOPS:

Lansing	762
th. 233'	
Base 995, no oil noted	
Kansas City	1050
th. 123'	
base 1173	
Bartlesville sand	1678

Best pay sand
1678-81, shy, low-med. por. & sat SFO