

14-22-11E
Greenwood

10" 1004 FARM Mellison
20" 8 1-4 1624 COMPANY
15 1-2 147 6 5-8 1678 CONTRACTOR
12 1-2 593 5 3-16 COMMENCED March 27, 1924.

NO. 3 COUNTY

COMPLETED April 28, 1924

		14	

TOTAL DEPTH SHOT 80 QUARTS BETWEEN 1806-1921'

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

ELEVATION INITIAL PRODUCTION 150 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS
REMARKS

Formation	Depth.
msd	8
lime white hrd	18
slate white sft	65
lime white hrd	90
slate blue sft	110
lime white hrd	115
slate light sft	147
lime white hrd	152
shale white sft	207
lime white hrd	222
slate black sft	227
lime white hrd	237
slate white sft	285
lime white hrd (Little water)	330
slate blue sft	370
lime white hrd	390
shale brown st	410
lime white hrd	415
shale black sft	455
lime white hrd	475
shale blue sft	495
lime white hrd	525
shale brown sft	593
lime white hrd	597
shale black sft	605
lime white hrd	640
shale brown sft	655
water sand light sft HW	935
early shale white sft	970
lime white hrd	1009
shale black sft	1014
lime white hrd	1024
water sand light sft 2 HW	1034
lime white hrd	1060
shale brown sft	1215
lime white hrd	1230
shale white sft	1260
lime white hrd	1385
shale black sft	1390
lime white hrd	1410
shale white sft	1530
lime white hrd	1535
shale black sft Cave	1650
lime white hrd	1560
shale white sft	1624
lime white hrd	1634
shale white sft	1840
broken sand white sft	1878
sand light sft	1926
Plugged back with limit plug, iron cuttings and lead plug to 1921.	