


P 15-22-11E

10" 990 FARM Bartlett NO: 3 COUNTY Greenwood
 20" 8 1-4 1412 COMPANY Empire Gas and Fuel.
 12 1-2 6 5-8 1877 CONTRACTOR E.P. Hudkins.
 12 1-2 6 20 5 3-16 COMMENCED 10/17/25 COMPLETED 11/9/25
 TOTAL DEPTH 1914 SHOT QUARTS BETWEEN



CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Empire Gas and Fuel

ElDorado, Kansas.,
 FIGURES INDICATE BOTTOM OF FORMATIONS.
 REMARKS

ELEVATION

INITIAL PRODUCTION after shot
 1st 24 hours 115 bbls. 115
 bbls water 2nd 24 hrs. 105
 Bbls Oil.

Formation	Depth
shale	20
lime	25
shale	75
lime	85
shale	100
shale	200
lime	225
shale	315
lime	350
shale	370
lime 2 BW	385
shale	405
lime	440
shale	490
lime	510
shale	585
lime	595
shale 1/2 BW 615	610
lime 625 12 1/2 csg	685
shale	845
water sand	865
sandy shale	955
shale HFW 845	970
lime	974
shale	997
lime 997 10" csg	1020
shale	1025
lime	1125
shale	1245
lime	1275
red rock	1280
lime HFW 1315-30	1315
sand	1330
lime	1335
slate white	1391
lime white	1403
slate black	1408
slate white	1415
1416 8" csg	
shale	1670
lime	1675

Formation	Depth.
shale blue	1790
lime shell white	1795
shale white	1805
slate black	1830
slate white	1835
slate white	1840
shale light	1880
T.S.	1874 S.L.M.
OIL Sand	1914 T.D.
shot between 1894 and 1914	
80 qts put in 11-10-25	

REMARKS.

At depth of 1910. Well was shut down for an hour to test water. no water came in hole at the end of the hour. so well was drilled 4 feet deeper to 1914. After standing 3 hours the bailer was run and it carried 1/2 bailer of salty wtr. Drilling was stopped at T.D. 1914 R.L.Kidd. Nov 9, 1925

Shot 80 qts from 1896-1914. Hole filled up with 500' fluid over night after shot est 150 wtr 300' oil. R.L.Kidd Nov 10, 1925

1 St hour 24 swabbed 115 bbls oil 115 H2O.
 2nd 24 hours " 105 " " 132 h2O