


10" 1010 FARM Ott NO. 1 COUNTY Greenwood.
 20" 8 1-4 1795 COMPANY Empire Gas and Fuel.
 15 1-2 6 5-8 2203 CONTRACTOR
 12 1-2653 5 3-16 COMMENCED 2-25-26 COMPLETED 4-21-26



TOTAL DEPTH 2226 1/2 SHOT 120 QUARTS BETWEEN 2174-2201
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Empire Gas and Fuel.
 Bartlesville, Okla.

ELEVATION 1144
 INITIAL PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS

Formation	Depth	Formation	Depth.
soil black	4	lime	1350
clay	8	shale	1355
lime	50	lime	1365
slate	70	shale	1390
lime	85	lime	1410
shale	110	shale	1450
lime	120	lime	1460
shale	160	shale	1575
lime white	170	black shale	1595
shale dark	180	grey sdy shale	1613
lime hard	190	black slate SLM	1775
shale soft	205	lime and shat	1792
lime hard	215	17BW per hr 1775-92	
shale soft	235	black slate	1795
lime hard	250	lime hard	1885
shale soft	270	sdv lime	1903
lime hard	280	HFW 1885-1905	
shale soft	355	lime	2040
lime	370	slate	2050
shale	380	lime	2065
lime	390	shale	2080
shale	410	lime	2096
lime	425	slate white	2155
shale	490	shale black	2171
lime	500	lime sand and chert	2172 C.M.
shale soft	600		2175 1/2 SLM
lime	605	oil sand 75' OIH	2179
sand HFW 605-640	640	sdv lime	2192
shale soft	690	no increase in oil	
lime hard	705	sand	2197 1/2
slate	715	no increase in oil	
lime	725	sand	2203 1/2 T.D.
shale	735	no increase in oil	
lime	790	shot 120 qts 2174-2201 April 7	
white slate	810	made 25 bbls oil 25 wtr on pump	
lime hard	820	Deepened April 21.	
white slate	825	sand	2218 1/2
lime	930	sdv lime	2226 1/2
sand 12BW per hr 930-45	945	Fluid remained same while deepening	
sandy lime	955	500' oil and wtr	
shale	1010	Tested 3B Oil 3BW per hr April 23	
lime hard O.M.	1015		
SLM 1010			
lime	1036		
small show oil 1036-42			
sdv lime	1062		
3BW per hr 1043-52			
lime 2BW 1076	1145		
show gas at 1075			
slate	1295		
lime	1315		
slate	1340		

- Base
 KC