

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. E. C. Murphy
Farm. Browning

No. 6

SEC. 18 T. 22 R. 10E
SW SW SE
1520' N. fr S. L. & 4190'
E. fr. W. L. SE/4

County Greenwood
KANSAS

Total Depth. 2400'


Comm. 10-3-57

Comp. 10-19-57

Shot or Treated.

Contractor. Jackman & Jackman

Issued. 11-30-57



CASING:

8 5/8" 207' cem. to surface 2400' w/75 sks. cem.

Elevation. _____

Production. 10 BOPD.

Figures indicate Bottom of Formations.

soil	4
clay	10
lime	20
shale & lime	80
shale	195
lime	215
shale	300
lime & shale	613
lime	630
lime & shale	810
lime	845
shale & lime	1135
shale	1330
sand	1450
lime	1605
shale	1710
lime	1900
shale & shells	2347
sand oil	2352
shale	2369
sand oil	2388
shale	2400
Total Depth	

TOPS SCOUT:

Lansing	1450
Bartlesville	2348

Perforated from 2370 to 2387 with
68 holes. Treatment 7000 lbs. sand
428 bbls. of water.

These measurements are all taken from
rotary kelly bushing which is 4' above
ground level.