


20" 10" 1147
15 1-2 1-4-1793
12 1-2 594 5 3-16 2083

FARM J.D. Clopton
COMPANY Mid-Continent Petroleum Corp.
CONTRACTOR Patten Drilling Co.
COMMENCED Aug 31, 1925

NO. 4 COUNTY Greenwood



TOTAL DEPTH 2136

COMPLETED Sept 21, 1925

SHOT QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Mid-Continent Petroleum Corporation. Eureka, Kansas.

ELEVATION

INITIAL PRODUCTION 60 Bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS

Formation	Depth	Formation	Depth
Black soil soft	10'	shale grey soft	1142
slate blue soft	100	lime white hard	1178 10" 1147
lime white hard	120	slate blue soft	1183
slate blue soft	170	lime white hard	1260
lime white hard	185	shale white soft	1345
slate white soft	195	lime blue hard	1355
slate blue soft	230	slate blue soft	1370
lime white hard	240	lime white hard	1410 2BW1400
slate blue soft	300	slate white soft	1420
shale grey soft	305	lime white hard	1430
lime white hard	315	shale white soft	1435
shale white soft	370	lime white hard	1510
slate and shells grey hard	400	slate blue soft	1515
shale grey hard	470	lime white hard	1560
lime white hard	490	shale white soft	1685
slate blue soft	495	lime white hard	1690
lime white hard	515	sd shale white soft	1715
shale brown soft	525	lime white hard	1730
lime white hard	535	sand white soft	1740 1 1/2 B.W
shale blue soft	560	shale dark soft	1755
lime grey hard	572 1 1/2 B.W	sand white soft	1760 wtr
shale blue soft	575	slate dark soft	1780
lime white hard	578	lime white hard	1795 8 1/2 1793
shale blue soft	580	shale blue soft	1810
lime white hard	590	lime white hard	1825
slate white hard	600	shale white soft	1830
set 12 1/2 at 594		broken line	1840
skate blue soft	602	shale white soft	1980
lime white hard	610	lime white hard	1985
slate blue soft	615	shale white soft	2015
lime blue hard	635	shale blue soft	2050
slate white soft	650	shale dark soft	2065
lime white hard	660	shale black soft	2081
slate blue soft	680	slate grey soft	2095
lime white hard	690	set 6-5/8 2083	
slate white soft	710	sand brown soft	2136 OIL
lime white hard	720	T.D.	2136
slate white soft	745		
lime white hard	755	Well completed for 60 Bbls.	
slate blue soft	765		
lime white hard	850		
blue soft slate	900		
lime white hard	905		
slate grey soft	1040		
lime white hard	1045		
1B.W.			
slate blue soft	1055		
sand white soft	1080 wtr		
slate blue soft	1085		
lime white hard	1090		
shale dark soft	1100		
lime white sdy	1140 HFV		