

WELL RECORD

J. D. Clopton Lease, Well #5

SW $\frac{1}{4}$ Sec 18-22-11 Greenwood County, Kansas. 990' From S & E Lines
 Drilling commenced Nov 30, 1925. Drilling completed Dec 22, 1925.
 Well drilled by Patton Drilling Company.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Soil, dark soft	0	3	
Mud, yellow soft	3	35	
Shale, blue soft	35	45	
Lime, white hard	45	50	
Slate, blue soft	50	75	
Lime, white hard	75	85	
Slate, light soft	85	115	
Lime, white hard	115	120	
Slate, blue soft	120	130	
Slate & shell,	130	190	
Slate, blue soft	190	215	
Lime, white hard	215	225	
Slate, blue soft	225	245	
Lime, white hard	245	255	
Slate, blue soft	255	265	
Lime, white hard	265	270	
Slate, white soft	270	300	
Lime, white hard	300	310	
Slate, blue soft	310	350	
Lime, white hard	350	358	
Slate, blue soft	358	365	
Lime, white hard	365	370	
Slate, blue soft	370	450	
Lime, white hard	450	490	
Slate, blue soft	490	540	
Lime, white hard	540	545	
Slate, black soft	545	550	
Lime, white hard	550	555	
Slate, white soft	555	575	
Sandy slate, brown soft	575	585	4 Blrs water per hour
Slate, blue soft	585	590	
Lime, white hard	590	595	
Slate, gray soft	595	615	
Lime, white hard	615	625	
Slate & shells	625	640	
Lime, white hard	640	655	
Slate & shells, gray	655	675	
Lime, white hard	675	710	
Slate, blue soft	710	720	
Lime, white hard	720	725	
Slate, blue soft	725	745	
Lime, white hard	745	755	
Slate, blue soft	755	770	
Lime, white hard	770	835	
Slate, dark soft	835	845	
Slate, gray soft	845	1025	
Lime, white hard	1025	1035	
Sand slate, brown soft	1035	1060	H F W
Lime, white hard	1060	1165	
Slate, blue soft	1165	1175	
Lime, white hard	1175	1260	3 Blrs water @ 1225'
Slate, blue soft	1260	1380	
Lime, Oswego, white hard	1380	1555	
Slate, blue soft	1555	1660	

WELL RECORD

J. D. Clopton

Well #5

Page 2

Lime, white hard	1660	1730	
Lime, broken, soft	1730	1740	3 Blrs water @ 1730'
Slate, blue soft	1740	1777	
Lime, white hard	1777	1810	
Slate, gray soft	1810	1950	
Slate, blue soft	1950	2075	
Sand, brown soft	2075	2104	
Shale, black soft	2104	2106	
Total Depth	2106		

Well completed for 35 Bbls.

CASING RECORD

12 $\frac{1}{2}$ "	Casing	615'	Pulled
10"		1160'	"
8 $\frac{1}{4}$ "		1777'	Left in hole
6-5/8"		2078'	" " "