

UNION NATIONAL BANK BLDG., WICHITA, KANSAS

Location NE cor SE SW

Sec. 19 T. 22 R. 11E.

Casing Record

County- Greenwood.

10" 1190 Farm- Greenwood No. 3-A  
 20" 8 1/2" 1774 SLM Company- T. K. Simmons.  
 15 1/2" 65/8" 2019 Contr.- The Skull Drlg. Co.  
 12 1/2" 585 53/16" Comm.- 7/28/1930. Comp.- 8/16/1930.  
 Total Depth 2102'. Shot 200 Quarts Between 2056-2099'.  
 Correspondence Regarding /This Well Should Be Referred to



Figures Indicate Bottom of Formations.  
 Date Issued. 8/30/1930.

Elevation  
 Initial Production 780 bbls.  
 22 hrs.

| Formation                  | Depth | Formation   | Depth |
|----------------------------|-------|---|-------|
| soil                       | 5     | sand gray HF <sup>W</sup>                               | 1165  |
| shale yellow               | 10    | lime white  | 1170  |
| shale blue                 | 40    | shale blue  | 1175  |
| lime lgt                   | 45    | lime white  | 1190  |
| shale drk                  | 70    | Pulled 10" straightreamed and re-run 10" csg. at 1190'. |       |
| lime lgt                   | 75    | lime lgt  | 1265  |
| shale lgt                  | 95    | shale gray  | 1370  |
| lime lgt                   | 135   | lime lgt  | 1390  |
| shale gray                 | 145   | shale drk   | 1395  |
| lime white                 | 155   | lime white  | 1545  |
| shale blue                 | 160   | 3 BW 1450-1475'   |       |
| lime white                 | 210   | shale gray  | 1660  |
| shale lgt                  | 250   | lime lgt  | 1665  |
| lime white                 | 255   | shale lgt curving                                       | 1690  |
| shale white                | 280   | lime white  | 1710  |
| lime white                 | 290   | shale white   | 1774  |
| shale gray                 | 355   | Ripped and started 10" pipe                             |       |
| lime lgt                   | 365   | Set 8 1/2" csg. at 1774' SLM                            |       |
| shale lgt                  | 440   | lime gray   | 1780  |
| lime white                 | 465   | shale drk   | 1800  |
| lime lgt                   | 485   | lime white  | 1805  |
| shale black                | 500   | shale blue  | 1815  |
| lime lgt                   | 510   | lime lgt  | 1820  |
| shale lgt                  | 540   | shale lgt   | 1830  |
| lime white                 | 555   | lime lgt  | 1850  |
| shale white                | 560   | shale lgt 1 BW  | 1875  |
| lime white                 | 570   | shale drk   | 1935  |
| sand gray 5 BW             | 575   | lime white  | 1940  |
| shale blue                 | 585   | shale sdy white   | 1965  |
| lime lgt                   | 595   | shale drk   | 1975  |
| shale gray                 | 605   | shale lgt SLM   | 2019  |
| lime white                 | 620   | Set 6 5/8" csg. at 2019'                                |       |
| shale blue                 | 640   | shale black   | 2032  |
| lime white                 | 650   | shale lgt   | 2053  |
| shale gray                 | 670   | sand oil  | 2102  |
| lime white                 | 675   | Some shale from 2088-2093'                              |       |
| shale blue                 | 745   | Total Depth   | 2102' |
| lime lgt                   | 750   |   |       |
| shale lgt                  | 765   |   |       |
| lime lgt                   | 795   |   |       |
| shale drk                  | 815   |   |       |
| lime white                 | 835   |   |       |
| shale blue                 | 845   |   |       |
| shale lgt                  | 945   |   |       |
| shale drk                  | 1010  |   |       |
| sand gray -HF <sup>W</sup> | 1045  |   |       |
| shale lgt                  | 1085  |   |       |
| shale drk                  | 1090  |   |       |
| sand                       | 1125  |   |       |
| lime lgt                   | 1135  |   |       |
| Set 10" csg. 1135'         |       |   |       |
| lime white                 | 1155  |   |       |
| shale black                | 1160  |   |       |