

Company- CITIES SERVICE OIL COMPANY
Farm- Greenwood Unit No. 6

SEC. 19 T. 22 R. 11E
NE NE SW
2310' N, 330' W, of S/4 corner

Total Depth. 2091

Cem. 3-12-53


Comp. 3-19-53

County Greenwood
KANSAS

Shot or Treated.

Contractor. Trans Era Petro. Inc. & Ark Valley Drlg. Co.

Issued. 12-19-53



CAJING:

8 5/8" 63,83' cem. w/40 sx

5 1/2" 2045' cem. w/100 sx

Elevation. 1194 RTB

Production. 2 BO 2 BW 24 hrs.

Figures indicate Bottom of Formations.

lime broken	16
shale	22
lime	26
shale	33
lime	52
shale	55
shale w/lime strks	150
shale & shells	1120
lime	1238
shale & lime	1350
lime	1510
shale & lime	2020
shale & sand	2055
sand	2091 RTD
Total Depth	

Tops:

Douglas Ss.	973
Base	1094
Lansing Lime	1094
Base	1246
Kansas City Lime	1346
Base	1534
Bartlesville Ss.	2046
Base	2078

Steel Line Measurement:

902=902

1355=1355

2037=2037

973' N.S.O.

1094' N.S.O.

1346' N.S.O.

2046' G.S.O.

Core #1 2037-55' (18') (17½' rec.) (½' lost)

Core #2 2055-73' (18') (18' rec.)

Core #3 2073-91' (18') (13½' rec.)

Bleeding Core:

2046-55' Poor to fair bleeding.

2055-73' Fair to good bleeding.

2073-78' Spotted fair bleeding.

2078-91' H.S.O.

T.D. 2091'

Best Pay 2046-78'

Drld. cem. plug & C.O. to R.T.D.

2091'

Bailed V.S.S.O.

P.B. w/rock to 2078'

Shot w/30 qts. 2057-78'

(no fluid noted)

Slight show oil & O wtr. (est.

1 gal oil) Set pumping unit.

Note: All measurements taken from RTB.