

19-22-118


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SUNRAY MID-CONTINENT OIL COMPANY
Farm- Harris No. W-5

SEC. 19 T. 22 R. 11E
NW NW NW
440' SNL & 50' EWL

County Greenwood
KANSAS/

Total Depth. 2091'
Comm. 2-6-57 Comp. 2-20-57
Shot or Treated.
Contractor. Jackman & Jackman
Issued. 5-25-57



Elevation. ?

Production. Water Input

CASING:

8 5/8" @84' cem. to surface
4 1/2" @2067' w/525 sx cem.

Figures indicate Bottom of Formations.

These measurements are all taken from RKB which is 4' above ground level.

soil	4
clay	26
shale	35
lime	41
lime & shale	90
shale & lime	185
shale	460
lime	478
shale	535
lime & shale	740
shale & lime	940
shale	1018
lime	1020
sand water	1115
lime	1270
shale	1355
lime	1545
shale & lime	1600
shale & shells	1830
shale	2066
sand oil	2085
shale	2091

Total Depth

TOPS
BARTLESVILLE 2066

Remarks

MOCT took 110 BW/3 hours
@110 psi. Water cut back
to 250 BW/24 hours.