

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location NW NE SW.

Sec. 2 T. 22 R. 3E.


Casing Record

10" 1312 Farm- Berns
 20" 8 1/4" 1790 Company- W. A. Cameron et al.
 15 1/2" 200 65/8" 2445 Contr.-
 12 1/2" 945 53/16" Comm.- 3/16/27.

County- Marion.

No. 1

Comp.- 10/19/27.



Total Depth 2708'. Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to

Elevation 1346

Figures Indicate Bottom of Formations.
 Date Issued. 4/12/1930.

Initial Production Dry.

Formation	Depth	Formation	Depth	Formation	Depth
soil	12	lime	750	slate	2210
lime	30	shale	780	Show oil	2236
slate	35	shale	790	lime	2245
lime	60	lime	800	shale	2255
red rock	65	shale	835	lime	2275
slate	80	lime	840	shale	2285
sand water	85	slate	865	brkn lime	2295
lime	115	sdv shale	945	lime	2300
shale	120	lime	950	shale	2340
red rock	130	shale	960	shale	2385
lime	155	lime	1015	lime	2400
sdv shale	165	shale	1018	slate	2435
shale	178	lime	1025	flint rock	2438
slate	180	slate	1048	shale HW	2445
lime	195	lime	1065	sand	2472
shale	207	shale	1071	red sand	2500
slate	211	lime	1080	chat all colors	
lime Water 220-65	220	shale	1165		2502
lime	230	lime	1180	water sand	2600
sdv shale	265	shale	1210	shale	2602
slate	293	lime	1235	sand & lime	2604
red rock	298	shale	1280	shale	2606
slate	310	lime	1312	shale	2708
lime & shells	315	shale	1320		
slate	330	8 BW 1325		T.D.	2708
lime	342	sand	1345		
slate	355	shale	1364		
sand	375	sand	1385		
slate	390	slate & lime	1405		
shale	395	lime	1420		
lime	405	shale	1440		
slate	420	lime	1455		
slate	465	shale	1473		
lime	470	lime	1525		
slate	478	shale	1570		
lime & shells	481	lime 8 BW	1580		
shale	507	sand	1600		
lime sdv	515	shale	1620		
slate	525	lime	1660		
red rock	540	shale	1720		
sdv lime	550	sand	1726		
sand 5 BW	565	shale	1786		
shale	573	lime	1793		
lime	580	shale	1820		
shale	588	lime	1830		
lime	590	shale	1885		
slate	598	lime	2025		
lime	603	shale	2030		
lime green	618	lime	2055		
shale	625	shale	2075		
sdv lime	635	lime	2090		
lime	640	slate	2105		
shelly	650	lime	2115		
sdv shale	680	brkn lime	2125		
lime	684	lime	2140		
shale	689	Shale break 2'			
lime	712	lime	2150		
shale	725	lime 1 BW	2160		
shale	745	lime	2205		