

CASING RECORD

LOCATION: 330 from S. Line 990 ft from W. Line.

SEC 20 T 22 R 10E

330 FSL, 990 FWL NE (?)

10" 1443 FARM J. A. Browning. NO. 23 COUNTY Greenwood
 20" 81-4 1765 COMPANY Sinclair Oil & Gas.
 15 1-2 111 6 5-8 1973 CONTRACTOR Geo. Bucklin
 12 1-2 434 5 3-16 2258 COMMENCED June 14, 1925 COMPLETED July 16, 1925
 TOTAL DEPTH 2347 SHOT QUARTS BETWEEN



CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

Sinclair Oil and Gas Co.

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

Tulsa, Okla.

INITIAL PRODUCTION

300 bbls.

REMARKS

| Formation | Depth | Formation | Depth. |
|-------------|-----------|------------------|-------------------|
| soil | 60 | shale | 1385 |
| lime | 70 10 BW. | lime | 1390 |
| sand | 80 Water. | shale | 1405 |
| lime | 105 | lime | 1535 3 Bbl water. |
| shale | 130 | shale | 1630 |
| lime | 150 | lime | 1755 |
| shale | 230 | black slate | 1765 5bbl Water. |
| lime | 255 | lime | 1820 |
| shale | 280 | slate gray | 2030 |
| lime | 295 | lime | 2040 |
| shale | 315 HFW | slate gray | 2125 |
| sand | 355 | shale brown | 2140 |
| shale | 400 | lime | 2145 |
| lime | 410 | slate blue | 2258 |
| shale | 431 | sandy lime | 2260 |
| lime | 455 | slate | 2277 |
| shale | 470 | sand | 2347 |
| lime | 510 | light brown sand | 2367 |
| shale | 580 | brown sand | 2340 |
| lime | 605 | white sand | 2347 T, D |
| shale | 635 | | |
| lime | 660 | | |
| shale | 720 | | |
| lime | 775 | | |
| slate | 785 | | |
| lime | 800 | | |
| slate | 820 | | |
| lime | 850 | | |
| shale | 855 | | |
| lime | 870 | | |
| shale | 885 | | |
| lime | 900 | | |
| sandy shale | 910 | | |
| lime | 945 | | |
| slate | 950 | | |
| lime | 965 | | |
| shale | 990 | | |
| lime | 995 | | |
| shale | 1005 | | |
| lime | 1010 | | |
| shale | 1030 | | |
| lime | 1045 | | |
| shale | 1070 | | |
| lime | 1075 | | |
| shale | 1085 | | |
| lime | 1100 | | |
| shale | 1115 | | |
| lime | 1130 | | |
| shale | 1150 | | |
| sandy shale | 1160 3BW | | |
| sand | 1170 | | |
| shale | 1230 | | |
| lime | 1240 | | |
| shale | 1260 | | |
| sand | 1300 HFW | | |
| shale | 1330 | | |
| lime | 1335 | | |
| shale | 1360 | | |
| lime | 1370 | | |

Shot Record.

SHOT #1 By American Torpedo Co.
 7-19-25. 10 qts size of shell
 2 1/2" x 10. Shot between 2332 & 2342
 Production increased 50 bbls.

SHOT #2 by Eastern Torp. Co.
 7-21-25. 20 qts Size of shell
 2 1/2" X 20. Shot beteen 2322-2342.
 Prod increased 25 bbls Anchor
 5' Cavings 0

SHOT #3 by Independent Torp Co.
 7-26-25 30 qts Size 3" x 14' & 2 1/2"
 x 10' Shot between 2318 & 2342.
 Prod. increased 25 bbl. Anchor,
 5' Cavings 0