

Well Log

Monroe Well #6A

Moved, rig up
 Cased 7' with 10"
 Size of hole 10"
 Surface pipe hung
 Ream out tight hole
 Set 218' 8" pipe
 7 bailers water per hour
 S.L.M. at 218'
~~21~~ Pipe never shut off
 Drove it a little and put in some shale
 Shut water off
 Refill socket
 Bailed hole dry
 Cleaned out 40' cave
 S.L.M. at 674'
 6 1/2" at 679'
 Cased from 0 to 679' with 6 1/2"
 S.L.M. 694'
 Pipe settled and drove 4 1/2"

S.L.M. at 733' 4"
 Cemented bottom back to 727' 6"
 Run tubing packer
 Rag packer at 708'
 Cemented 3 sacks cement thru' 1"
 Cemented above packer 683
 Run 6 1/2"
 Pulled 6 1/2", started 8"
 Pulled 8" - Tear down and moved

Thick- ness	Strata	Total Depth
2	Soil	2
16	Lime	18
80	Shale	98
7	Lime	105
5	Shale	110
46	Lime	156
6	Shale, black water	162
17	Lime	179
4	Shale, water	183
5	Lime	188
4	Shale	192
14	Lime	206
12	Shale S.L.M.	218
69	Shale	387
3	Lime	390
5	Shale	395
9	Lime	404
31	Shale	435
15	Sand, water	450
13	Shale	463
2	Lime	465
5	Shale	470
8	Lime	478
14	Shale	492
7	Lime	499
22	Shale	521
2	Lime	523
8	Shale	531
10	Lime	541
15	Shale	556
8	Lime	564
10	Shale, black	574
2	Shale	576
2	Lime	578
7	Shale, Black, hard	585
3	Lime	588
6	Shale, black	594
20	Shale, dark	614

Thick- ness	Strata	Total Depth
26	Shale, Light	640
5	Shale, dark	645
5	Shale, black	650
10	Shale, light	660
10	Shale, dark	670
9	Shale, light	679
21	Shale	690
4	Sand carried oil	694

June 23, 1947 - July 9, 1947

October 20, 1950 - Wash and acidize

12-5-53

Dowell pumped 2000# sand and 77Bbls oil

July 29, 1954 - Pumped in 20 sacks of cement to plug.