

Kimzey Drilling Co.

License #33030

Start Date: 04/01/03

End Date: 04/03/03

Marvin Kimzey
P.O. Box 131
La Cygne, KS 66040

RJ Enterprises
1203 East 4th Avenue
Garnett KS. 66032
Miller 1W API #15-107-23674-00-00

<u>Thickness of Strata</u>	<u>Strata Formation</u>	<u>Total Depth</u>
1	soil	1
5	clay	6
49	lime	55
9	shale	64
15	lime	79
4	shale	83
25	lime	108
167	shale	275
25	lime	300
58	shale	358
14	lime	372
11	shale	383
4	lime	387
37	shale	424
24	lime	448
8	shale	456
8	lime	464
91	shale	555
2	lime	557
64	shale	621
1	lime	622
14	shale	636
2	broken sand	638
10	oil sand	648
1	shale	649T.D.

Drilled 10 1/4ft. hole 20' set 20' of 7" surface w/6 sacks of cement. ✓

Drilled 5 5/8 hole to 636' and cored from 636' to 649' and run 27/8 pipe to 636' with packer.