

Kimzey Drilling Co.

License #33030

Start Date: 03/15/03

End Date: 03/24/03

Marvin Kimzey
P.O. Box 131
La Cygne, KS 66040

RJ Enterprises
1203 East 4th Avenue
Garnett KS. 66032
Weber 2W API #15-107-23705-00-00

<u>Thickness of Strata</u>	<u>Strata Formation</u>	<u>Total Depth</u>
2	soil	2
49	lime	51
7	shale	58
22	lime	80
4	shale	84
26	lime	110
24	shale	134
2	lime	136
141	shale	277
25	lime	302
57	shale	359
14	lime	373
13	shale	386
4	lime	390
35	shale	425
24	lime	449
9	shale	458
6	lime	464
91	shale	555
1	lime	556
62	shale	618
1	lime	619
15	shale	634
3	broken sand	637
10	oil sand	647T.D.

Drilled 10 1/4ft. hole 20' set 20' of 7" surface w/6 sacks of cement. ✓
Drilled 5 5/8 hole to 635' and cored from 635' to 647' and run 27/8 pipe to 635' with packer.