

2-22-22E

DRILLED FOR: DON L. THOMPSON
LINN COUNTY, KANSAS
SEC 2 TWP 22 REG 22E
SW SW

FARM: HARRY PADDOCK
WELL: #1

JUNE, 1972

RECEIVED
STATE CORPORATION COMMISSION

APR 8 - 1974


CONSERVATION DIVISION
Wichita, Kansas

API#15-107-20508

THICKNESS	FORMATIONS	TOTAL DEPTH
3	soil	3
44	lime	47
4	shale black	51
24	lime	75
3	shale black	78
2	lime	80
3	shale	83
17	lime	100
10	shale blue	110
165	shale w/ lime st	275
40	lime	315
15	shale	330
16	shale w/ lime st	346
12	lime	358
52	shale w/ lime st	410
25	lime w/ shale st	435
108	shale	543
3	shale black	546
49	shale	595
28	dark shale	623
8	shale w/ lime st	631
50	dark shale	681
5	shale black	686
10	shale	696
14	sand light gas odor	710
10	sandy shale	720
12	sand light odor	732
8	sand light show	740
14	sand broken light show	754
31	sand odor	785
2	chat	787
124	miss lime & churt	912

T.D.

Pulled drillpipe to 750' spotted 5 sacks cement
Pulled pipe to 175' spotted 8 sacks
Bridge @ 20' 3 sacks to surface.



Geological Survey
WICHITA, BRANCH