

Company Claude Crowder

Sec. 2 T. 22 R. 22E

Farm Ed McGee

No.

Loc. SE/4
County Linn

Total Depth


Comm. May 14, 1941

Comp.

Shot or Treated

Contractor

Issued



Casing

20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation

Production

*Gift From
Claude Crowder.*

Figures Indicate Bottom of Formation

3	Soil	3	
15	Lime Shells	18	
4	Shale	22	
10	Lime	32	
3	Shale	35	
15	Lime	50	
4	Shale	54	
21	Lime	75	
154	Shale	229	
3	Lime	232	
10	Sand	242	
3	Sandy Shale	245	
10	Lime	255	
5	Shale	260	
10	Sandy Shale	270	
35	Shale	305	
20	Lime	325	Gas
3	Shale Brown	328	
12	Lime	340	Gas
32	Shale	372	
30	Lime	402	
7	Black Shale Ft Scott	409	
3	Lime	412	2 Bailers
8	Shale	420	Water 380'
10	Sand	430	
80	Shale	510	
2	Lime	512	
18	Shale	530	
10	Black Shale	540	
30	Blue Shale	570	
10	Black Shale	580	
15	Gray Shale	595	
20	Black Shale	615	
15	Light Shale	630	
15	Sandy Lime	645	
10	Sandy Shale	655	
5	Shale	660	
4	Broken Sand	664	
31	Sand Gas	695	

Total depth 695
 Run 618' 6 1/4 casing
 660' 2" tubing
 2' packer (mud packer)
 2' perfration

31 Anchor