

1930

COPY

SIDE ONE

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
ACO-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

Operator: License # 9102Name: MICO Oil and Gas, Inc.Address Post Office Box 281City/State/Zip Paola, Kansas 66071Owner: Crude MarketingOperator Contact Person: Ernie D. PrattPhone (913) 755-2128

Fractor: Name: _____

License: _____

Wellsite Geologist: _____

Designate Type of Completion

☒ New Well ☐ Re-Entry ☐ Workover☒ Oil ☐ SWD ☐ Temp. Abd.☐ Gas ☐ Inj ☐ Delayed Comp.☐ Dry ☐ Other (Core, Water Supply, etc.)

If OWM: old well info as follows:

Operator: _____

Well Name: _____

Comp. Date _____ Old Total Depth _____

Drilling Method:

☐ Mud Rotary ☐ Air Rotary ☐ Cable1/9/911/12/913/7/91


Spud Date

Date Reached TD

Completion Date

API NO. 15- 107-23,239County LinnSE SW NW-KCC ☒ East
SW/4 SE/4NW/4 Sec. 18 Twp. 22 Rge. 22 West2805 Ft. North from Southeast Corner of Section3685 Ft. West from Southeast Corner of Section

(NOTE: Locate well in section plat below.)

Lease Name Mitchell Well # 1-90Field Name Blue MoundProducing Formation BartlesvilleElevation: Ground 1000 KB _____Total Depth 663.0 PBID 659.0

3-22-91

Amount of Surface Pipe Set and Cemented at 20 FeetMultiple Stage Cementing Collar Used? ☐ Yes ☒ No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from 663.0feet depth to 659.0 w/ 78 sx cmt.

INSTRUCTIONS: This form shall be completed in triplicate and filed with the Kansas Corporation Commission, 200 Colorado Building, Wichita, Kansas 67202, within 120 days of the spud date of any well. Rule 82-3-130, 82-3-107 and 82-3-106 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107 for confidentiality in excess of 12 months. One copy of all wireline logs and drillers time log shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells. Any recompletion, workover or conversion of a well requires filing of ACO-2 within 120 days from commencement date of such work.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature Ernie D. PrattTitle President Date 3/14/91Subscribed and sworn to before me this 14 day of March, 19 91.Notary Public Sandra J. SchweerDate Commission Expires 9-19-94

SANDRA J. SCHWEER

My Appt. Exp. 9-19-94

K.C.C. OFFICE USE ONLY

F ☐ Letter of Confidentiality Attached
C ☒ Wireline Log Received
C ☐ Drillers Time Log Received

Distribution

☐ KCC ☐ SWD/Rep ☐ NGPA
☐ KGS ☐ Plug ☐ Other (Specify) FS

COPY

18-22-22E

CHASE DRILLING

Well No. # / Location
 Operator Mico Oil Gas Address Paola KS. 66071
 Lease Mitchell County Linn
 Contractor Michael Chase Casing

DEPTH		FOOTAGE	DESCRIPTION
from	to		
0	20	20	Surface Casing
20	56	36	Limestone
56	63	7	Dark Shale
63	85	22	Limestone
85	88	3	Dark Shale
88	95	7	Limestone
95	98	3	Dark Shale
98	112	14	Limestone Shale Streaks
112	232	120	Gray Shale
232	271	39	Sandy Shale
271	283	12	Green Shale
283	307	24	Lime Shale Streaks
307	311	4	Green Shale
311	319	8	Sand Some Shale
319	363	44	Sandy Shale
363	377	14	Limestone Shale Streaks
377	387	10	Shale
387	394	7	Lime Shale Streaks
394	423	29	Shale
423	447	24	Lime
447	455	8	Dark Shale Coal
455	460	5	Lime
460	464	4	Dark Shale Coal
464	632	168	Shale
632	633	1	Oil Sand Good Show Odor
633	643	10	Oil Sand Good Show Odor
643	655	22	Shale

Seating nipple 629'

Ran 659' 2⁷/₈ upset tubing

COPY

18-22.22E

CORE TIMES

633-634--1:31
634-635--2:27
635-636--1:34
636-637--1:45
637-638--3:06
638-639--2:11
639-640--2:32
640-641--3:14
641-642--1:42
642-643--1:52
643-644--2:09
644-645--2:43
645-646--3:23
646-647--3:41
647-648--4:22
648-649--4:51
649-650--8:14
650-651--9:27

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1991

CONSERVATION DIVISION
Wichita, Kansas