

CASING RECORD

LOCATION 2310' fr NL 350' fr SL
330' fr EL 990' fr WL

SEC 22 T 22 R 11 E.

10" 1049

FARM Gravatt

NO. 3

COUNTY

Greenwood.

20"

8 1-4

1638

COMPANY

Phillips Petroleum Co.

15 1-2

6 5-8

1943

CONTRACTOR

12 1-2

641

5 3-16

COMMENCED

2-16-25

COMPLETED

3-5-25.

22

TOTAL DEPTH

SHOT

QUARTS BETWEEN

1912'-1941'

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

Plotted L.R.

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS

INITIAL PRODUCTION 63 bbls.

REMARKS

Formation	Depth	Formation	Depth
top soil dark soft	4	slate dark sft	1275
lime white hrd	15	lime white hrd	1300
slate blue sft	40	slate gray sft	1310
lime white hrd	50	(3 BW at 1300')	
slate white sft	70	lime white hrd	1470
lime white hrd	75	slate dark sft	1600
slate dark sft	100	lime white hrd	1605
lime white hrd	110	shale white sft	1615
slate sft	120	lime white hrd	1620
lime white hrd	125	shale light sft	1635
slate white sft	150	(8" at 1635' S. L.)	
slate white sft	175	lime white hrd	1640
lime white hrd	185	shale dark sft	1720
slate white sft	216	shale white sft	1730
slate dark sft	240	lime white hrd	1735
lime white hrd	245	shale dark sft	1750
slate dark sft	315	shale dark sft	1880
slate dark sft	345	sand shells & slate d. sft	1910
lime white hrd 1 BW 400'	385	sand shells & shale blue sft	1925
slate white sft	390	broken sand gray sft	1920
lime white sft	400	oil sand	1940
slate dark sft	440	red shale blue sft	1962
lime white hrd	455	broken sand gray sft 1976	1976
slate white sft	470	Plugged back to 1943' from	1976'
lime white hrd	480		
slate brown sft	490	6" csg. set on bottom 1943' with two	
lime white hrd	510	bottom joints perforated.	
slate white sft	540		
lime white hrd	550	Soft gray, true sand at 1925 to 1940.	
slate dark sft	570	Show of oil. Broken gray sand soft	
lime white hrd	600	1962' to 1976'. No oil and a little	
(12" 640 S. L.)		water.	
slate white sft	640		
lime white hrd	695		
slate dark sft	705		
lime white hrd	730		
slate white sft	780		
slate dark sft	810		
lime white hrd	825		
slate dark sft	865		
lime white hrd	875		
(HFW at 880')			
slate brown sft	880		
water sand white sft	930		
slate dark sft	945		
sand white hrd	950		
slate white sft	990		
lime sandy hrd	1010		
slate white sft	1025		

(10" at 1059' SL.

slate dark sft	1045
lime white hrd	1070
slate dark sft	1085
lime white hrd	1175
(4 BW at 1299')	