

Ford (formerly Mullins).

NE $\frac{1}{4}$ Sec. 21 & W $\frac{1}{2}$ NW $\frac{1}{4}$ Sec. 22-22-23 E. Linn County, Ks. 300 acres.

Commenced drilling Feb. 6, 1937. Finished Feb. 18, 1937. Al Broesach

Thickness of Strata	Formation	Total Depth	Remarks
9	Soil	9	
11	Lime	20	
3	Shale black	23	
2	Lime	25	
2	Shale	27	
8	Lime	35	
3	Shale	38	
10	Lime	48	
12	Shale	60	
4	Lime	64	
5	Shale	69	
10	Shale sandy	79	
103	Shale	182	
8	Red rock	190	
13	Shale blue	203	
25	Lime shelly	228	
11	Lime	229	
46	Shale	275	
5	Sand broken	280	
10	Shale	290	
5	Lime	295	
1	Shale black	296	Little gas
11	Lime	311	
1	Lime	312	
9	Shale	321	
5	Lime	326	
4	Shale dark	330	Little gas
25	Shale blue	355	
10	Shale white	365	
7	Lime broken	372	S.L.M. 371
12	Lime	384	
2	Shale black	386	Little gas
5	Shale blue	391	
4	Lime	395	
9	Shale	404	
3	Lime	407	
9	Shale	416	Gas 6" in 1" @ 418
8 $\frac{1}{2}$	Sand	424 $\frac{1}{2}$	" 8" " 106,000

10' 8 $\frac{1}{2}$ " casing. 6 $\frac{1}{2}$ " packer set at 406'. 1" pony packer set @ 396'

15' 9" anchor. 2" perforation. packer set 406. 547' 2" of 1" tubing.

489' 9" 2" tubing.