

Ford

Ford

WELL LOG

Well #2, Section 21-22-23, Linn County, Kansas.
 Finished drilling March 22, 1928.

Formation	Thickness	Total Depth	
Soil	3	3	
Lime	17	20	
Shale	3	23	
Lime	25	50	
Shale	10	60	
Lime	5	65	
Shale	135	200	
Lime	35	235	
Shale	55	290	Gas bubbles at 250 and 290
Lime	15	305	
Shale	10	315	
Lime	10	325	Gas 2" in water 2" 315 to 320
Shale	35	360	
Lime	20	380	
Shale	7	387	gas 1" Merc. in 2" (Steel Line)
Lime	3	390	
Shale	20	410	
Sand	15	425	very small showing of oil Gas 1.4" merc. in 2"
Shale	15	440	
Sand	5	445	Gas 1.8" merc. in 2"
Sand Broken	15	460	Small showing of oil
Shale	70	530	
Sand	30	560	Gas and oil very small showing
Shale	5	565	
Sand	15	580	
Shale	100	680	
Sand - water	20	700	(Steel Line)

Hole plugged back to 423
 Cage on 2", 417
 8 1/2 x 2 Robinson packer set at 365
 Perforated nipple on 1" bottom 417
 1.4" merc. in 2" tubing
 11" " " 1" "
 Pressure 80 1/2
 8 1/2" drive pipe, 14'
 6 1/2" casing, 600 ft. drawn
 2" tubing, 423 "
 1" tubing, 421 "

