

Company

Farm D. L. Ford

No. 4

Sec. 22
Loc.

22 - 22 - 23 E

T. 22 R. 23

Total Depth

Comm. 4/15/37

Comp. 4/27/37


County

Linn

Shot or Treated

Contractor Albert Breisach

Issued



Casing

20 in.

10 in.

15 1-2

8 1-4

Elevation

12 1-2

6 5-8 1/4" casing 3' 6"

Production DRY

13 3-8

5 3-16 1/4" casing 300'

Figures Indicate Bottom of Formation

Kind of Rock	Total Depth	REMARKS
Soil	3	
Lime	8	
Shale	10	
Lime	13	
Shale	22	
Lime	32	
Dark Shale	37	Little Water
Lime	39	
Shale	53	
Lime H	63	
Shale	195	
Red Rock	202	
Shale	212	
Shale	219	
Lime Shells	243	
Lime	254	
Sand	269	
Sandy Shale	274	
Shale	287	
Shady Sand Lb+	311	Shady Sandy 296
Dark Shale Mulb	313	S.L.M. at 300 ft
Lime	318	Set 6 1/4 at 300 ft.
Shale Pison	319	
Lime	330	
Shale	341	
Lime	346	
Dark Shale	352	Little gas
Blue Shale Lb+	377	
White Shale	385	
Shelly Lime	392	Little Water
Lime	404	
Black Shale	407	Little Gas & water
Blue Shale	412	
Lime	413	
Light Shale	436	

Company

Farm

Ford

No.

4

Sec.

Loc.

T.

R.

22 - 22 - 23E

Total Depth

Comm.


Shot or Treated

Contractor

Issued

Comp.

County



Casing

20 in.

10 in.

15 1-2

8 1-4

12 1-2

6 5-8

13 3-8

5 3-16

Elevation

Production

Figures Indicate Bottom of Formation

FORD NO. 4 Page #2

Kind of Rock	Total Depth	REMARKS
Sand	441	S.L.M. at 438½,
Shale	443	Water at 460.
Sand	470	
Sandy Shale	472	

DRY HOLE

Well filled up 75 ft. from bottom with Shale. Bridge at 300 ft. Filled up with Shale 30 ft. Put in bridge at 27 ft. Filled to top of hole.