

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location SW SW SW


Sec. 24 T. 22 R. 12 E.

Casing Record

20" 10"  
 15 1/8" 8 1/2"  
 12 1/2" 65/8"  
 12 1/2" 53/16"

Farm- Frankhauser No. 5  
 Company- Darby Petroleum  
 Contr.-  
 Comm.- Nov. 4, 1927. Comp.- 11/25/27.

County Greenwood.



Total Depth 1665'  
 Shot Quarts Between  
 Correspondence Regarding This Well Should Be Referred to

Figures Indicate Bottom of Formations.  
 Date Issued. 5/12/28.

Elevation 1144  
 Initial Production 175 bbls.

Formation	Depth	Formation	Depth
soil	5	lime	1020
clay	10	slate	1030
slate	13	lime	1045
gravel	15	slate	1050
lime	25	lime	1075
blue slate	50	slate	1245
grey slate	65	lime	1260
lime	75	slate	1303
slate	100	lime	1305
lime	105	slate	1310
slate	175	lime	1315
lime	200	slate	1320
slate	250	lime	1325
lime	265	slate	1336
slate-	295	lime	1340
lime	335	slate	1355
slate	545	lime	1370
sand HFW	590	sdv slate	1400
slate	620	light slate	1550
lime	628	drk slate	1595
water sand	638	light sdv slate	1622
sdv lime	655	1st oil	
lime	658	brown oil sand	1662
slate	685	drk slate	1665
lime	692		
slate	700	Total Depth	1665'
Big lime	825		
slate	830		
lime	906		
blue slate	915		
grey slate	920		
red rock	922		
slate	969		