

## UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location NE cor SW/4


Sec. 26 T. 22 R. 12E

County Greenwood.

## Casing Record

	10"	955	Farm-	Fankhauser	No. 1
20"	8 $\frac{1}{2}$ "	1319	Company-	T. K. Simmons.	
15 $\frac{1}{2}$ "	46	65/8"	1732	Contr.-	Patton Drilling Co.
12 $\frac{1}{2}$ "	657	53/16"		Comm.-	4-11-28. Comp.- 4-29-28.
Total Depth	1788'			Shot	Quarts Between

Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.

Elevation Initial Production Dry.

Date Issued. 5/19/28.

Formation	Depth
gravel brown sft	46
Set 15 $\frac{1}{2}$ " pipe at 46'	
lime white hrd	60
slate blue sft	80
lime white hrd	90
slate blue sft	115
lime white hrd	125
slate white sft	170
lime white hrd	185
slate grey sft	195
lime white hrd	200
slate white sft	260
lime white hrd	270
slate white sft	290
lime white hrd	325
slate blue sft	345
lime white hrd	355
slate white sft	370
lime white hrd	375
slate white sft	530
lime white hrd	535
sand white sft HFW	555
sandy lime white hrd	595
slate blue sft	615
sandy slate lgt sft	630
sand light sft	645
lime white hrd	830
Set 12 $\frac{1}{2}$ " csg. at 656'	
slate blue sft	835
lime white hrd	845
slate blue sft	850
lime white hrd HFW	880
sand white sft	895
lime white hrd	910
slate blue sft	930
lime white hrd	935
slate blue sft	950
lime white sft	1010
Set 10" csg. at 958'	
slate blue sft	1020
lime white hrd	1030
sandy lime white sft	1040
2 BW PH	
lime white hrd	1070
slate blue sft	1220
lime white hrd	1240
slate white sft	1320
lime white hrd	1330
Set 8 $\frac{1}{2}$ " csg. at 1319'	
slate blue sft	1345
lime white hrd	1350
slate white sft	1585
slate light sft	1600
slate black sft	1660
slate light sft	1730
chat light sft	1740
Set 6 5/8" csg. at 1730'	
lime white hrd	1787
sand white sft	1788
Total Depth HFW	1788