

UNION NATIONAL BANK BLDG WICHITA, KANSAS


Location NW/c SE/4 SW/4

Sec. 29 T. 22 R. 13E.

Casing Record

County- Greenwood.

10" Farm- Luthi No. 4
 20" 3" Company- Simmons & Rhodes.
 15 1/2" 65/8" Contr.- Shull Drlg. Co.
 12 3/8" 53/16" Comm.- 2/25/1929 Comp.- 3/20/1929.
 Total Depth 1749'. Shot 40 Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.
 Date Issued. 4/13/1929.

Elevation Initial Production 40 bbls.

Formation	Depth	Formation	Depth.
cellar	5	shale white	790
lime white	30	lime grey	800
shale blue	35	lime white	860
lime white	55	shale white	870
shale blue	65	lime grey	900
lime white	75	lime white	920
shale blue	80	lime sdy	935
lime white	85	shale white	945
red rock	100	shale white	950
lime white	110	red rock	955
shale grey	115	shale white	960
lime white	125	set 10" casing 960 feet.	
shale blue	135	shale grey	995
lime white	170	limewhite	1000
shale blue	180	lime grey	1015
shale white	200	lime white	1050
shale grey	205	5BW 1035-45	
lime white	215	shale grey	1075
shale grey	298	lime white	1090
set 15 1/2 casing 298 feet.		shale dark	1095
shale grey	300	lime white	1105
lime white	310	shale grey	1240
shale blue	330	lime white	1245
lime grey	350	shale dark	1265
shale blk	355	lime white cave	1290
lime white	360	shale blk	1295
lime white	380	shale white	1325
shale grey	410	lime white	1330
shale blue	420	shale blue	1345
lime white	425	lime white	1355
shale blue	435	sand dark 7BW	1360
shale grey	560	lime white	1365
shale white	568	set 8 1/2 casing 1365	
lime grey	570	shale grey	1400
sand white HFW	590	shale white	1450
shale sdy	600	sand grey 1BW	1465
shale blue	610	shale grey	1500
lime white	625	shale white	1525
shale sdy	655	shale blue	1565
shale blue	680	shale dark	1625
lime grey	690	shale grey (SLM)	1657
lime white	700	set 6-5/8 pipe at 1657 SLM	
shale dark	710	shale sdy	1687
lime white	720	sand oil	1697
shale blue	730	shale dark	1749D
lime white	755	Plugged back to 1699.	
shale white	758		
set 12 1/2 casing 758			
shale white	760		
lime white	780		