

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location SW NW SE

Sec. 29 T. 22 R.13E

Casing Record

10" 1005
20" 8 1/2" 1547
15 1/2" 65/8" 1663
12 1/2" 640 53/16"

Farm- Silas Blanck No. 1
Company- The Texas Co.
Contr.- G.W. Hinkle.
Comm.- 3-31-30

County- Greenwood

Total Depth 1696' SLM

Shot 80 Quarts Between 1675-95.

Correspondence Regarding This Well Should Be Referred to



Elevation

Initial Production 60 bbls.

Figures Indicate Bottom of Formations.

Date Issued. 5-31-30.

Formation	Depth	Formation	Depth	Formation	Depth
soil clay yellow		lime wh hrd	972	sand grey sft	1666
sft	16	shale blue sft	979	Show oil 1663-66'	
lime wh hrd	40	red rock red sft	990	sand grey sft	1673
shale lgt sft	45	shale blue sft	1005	Better show 1666-73'	
lime wh hrd	55	lime grey hrd	1008	sand Bartlesville	
shale drk sft	67	shale blue sft	1020	brown sft	1690
lime grey hrd	85	lime grey hrd	1050	Bartlesville Good	
shale blue sft	100	shale blue sft	1056	1673-1690'	
lime grey hrd	112	sdv lime brown sft		sand shaley grey	
shale lgt sft	135		1073	sft	1695
lime grey hrd	143	shale lgt sft	1075	shale grey sft	1696
shale lgt sft	155	lime, shells & shale		Getting thinner 90-95.	
lime grey hrd	170	hrd grey	1080	shale 1695-96'	
shale blue sft	175	lime grey hrd	1085		
lime grey hrd	180	shale blue sft	1095	Total Depth SLM	1696
shale lgt sft	186	1 BW 1095'			
lime grey hrd	200	lime wh hrd	1110		
shale lgt sft	230	shale lgt sft	1115		
lime grey hrd	240	lime wh hrd	1125		
shale blue sft	260	shale blue sft	1130		
lime grey hrd	265	lime grey hrd	1135		
shale blue sft	327	shale blue sft	1260		
lime grey hrd	335	lime grey hrd	1264		
shale blue sft	350	shale lgt sft	1273		
lime grey hrd	376	lime grey hrd	1280		
shale brown sft	380	Hole caving 1280'			
lime blk hrd	388	shale blue sft	1290		
shale blue sft	402	2 BW 1290'			
lime grey hrd	423	lime grey hrd	1306		
shale lgt sft	600	shale blue sft	1311		
lime wh hrd	605	lime grey hrd	1315		
sand wtr greysft	635	sdv shale lgt sft	1345		
HPW 610; 8 BWP 635'		shale grey med.	1350		
shale blue sft	700	lime grey hrd	1355		
lime grey hrd	710	shale blue sft	1375		
shale blue sft	712	lime wh hrd	1378		
lime wh hrd	727	shale drk sft	1384		
shale lgt sft	729	3 BW 1380'			
shale drk sft	740	lime lgt hrd	1393		
lime grey hrd	745	shale lgt sft	1410		
sdv shale blue sft		lime lgt hrd	1420		
	755	shale lgt sft	1435		
lime grey hrd	790	lime blk hrd	1440		
shale lgt sft	810	shale blue sft	1480		
lime grey hrd	840	wtr sand lgt sft	1490		
lime wh hrd	880	7 BW 1380-1490'			
shale lgt sft	905	sdv shale lgt sft	1520		
lime wh hrd	959	shale Various sft	1660		
shale blue sft	969	sdv shale sft	1663		