


UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location NE/c NE/4 SE/4

Sec. 30 T. 22 R. 13E.

Casing Record
 10" 1000 Farm- Schwab No. 5 County- Greenwood.
 20" 8 1/2" 1401 Company- T. K. Simmons & D. M. Rhodes.
 15 1/2" 231 65/8" 1648 Contr.- Patton Drilling Co.
 12 1/2" 690 53/16" Comm.- 7-18-28. Comp.- 8/1/1928.
 Total Depth 1697' Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations. Elevation
 Date Issued. 9/22/1928. Initial Production 400 bbls.

Formation	Depth	Formation	Depth
soil	6	lime white	1060
lime white	35	Set 10" csg. at 1003'	
slate black	50	slate black	1065
lime white	60	lime white	1070
slate black	65	lime sandy white 3 BW	1085
lime white	70	shale sandy white	1120
slate gray	75	shale sandy gray	1260
lime white	90	lime white	1265
slate black	105	slate white	1275
lime white	110	lime white	1290
slate black	130	slate gray	1330
lime white	135	lime white	1335
slate gray	150	slate white	1350
slate & shells	185	lime white	1354
slate gray	205	slate black	1358
lime white	215	lime white	1362
slate gray	220	slate gray	1367
lime white	225	lime white	1374
slate white	305	slate white	1402
Set 238' of 15 1/2" csg.		lime white	1407
lime pink	315	Set 8 1/4" csg. at 1407'	
slate gray	340	slate gray	1425
lime white	355	slate black	1645
slate black	375	Set 6 5/8" csg. at 1644'	
lime white	400	sand brown	1696
slate gray	425	slate black	1697
lime white	435		
slate gray	570	Total Depth	1697
lime white	580		
slate gray	590	First oil at 1650'.	
sand gray HFW	625		
slate blue	645		
sand gray	684		
lime white	710		
Set 699' of 12 1/2" csg.			
slate black	720		
lime gray	730		
slate gray	735		
lime white	770		
slate white	785		
lime white	865		
slate gray	870		
lime white 4 BW	920		
lime sandy white	940		
lime white	945		
slate gray	950		
red rock	965		
slate black	1001		