


UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD LOCATION Lot 62. 10'N of Mo. Pacific SEC 30T22 R 13E.

10" 1038 FARM Townlot R. of Way.
 8 1-4 1473 COMPANY Kansan Oil Corp. and Pryor & Lockhart. NO. 1 COUNTY Greenwood
 15 1-2 6 5-8 CONTRACTOR Abell and Shull.
 12 1-2 73 5 3-16 COMMENCED Nov 3, 1927 COMPLETED Dec 12, 1927
 TOTAL DEPTH 1734 SHOT QUARTS BETWEEN
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO



FIGURES INDICATE BOTTOM OF FORMATIONS.
 REMARKS 12/24/27

ELEVATION
 INITIAL PRODUCTION Dry
 (Scout ticket)

Formation	Depth	Formation	Depth.
shale and shells	25	lime white	895
shale blue	40	shale grey	903
lime blue	45	lime grey	960
shale blue	50	Hole full water	935
shale blk	55	lime white	985
lime white	60	shale grey	990
shale blue	65	lime grey	997
lime brown	90	red rock	1008
shale grey 1B ^W	100	shale blue	1020
shale white	120	shale grey	1038
lime grey	135	run 10" casing at	1038
shale blk	145	lime grey	1060
lime white	155	shale dark	1065
shale blue	160	lime white	1160
lime grey	165	shale light	1205
shale blue	175	shale	1310
lime blue	178	lime	1335
shale blue	188	shale light	1365
lime blue	200	lime	1375
shale white	210	shale blue	1385
lime white	225	lime	1395
shale blk	235	shale dark	1400
lime white	245	shale grey	1473
shale white	250	run 8 1/4" casing	1473
lime white	260	lime broken	1483
shale white	280	shale brown	1490
lime grey	285	shale grey	1605
shale blue	340	shale blue	1625
lime grey	350	shale light	1645
shale blue	370	shale blk	1655
lime white	395	lime	1660
shale blk	410	shale sdy	1666
lime white	430	reduced hole at	1666 feet.
shale light	465	sdv shale	1720
lime grey	470	sand showing oil	1728
shale grey	500	shale sdy	1734
shale blk	615	steel line run at	1728
sand grey HF ^W	645		
shale white	657		
lime white	680		
sand grey water	693		
shale blue	696		
sand grey water	727		
lime blue	737		
rub 12 1/2" pipe at	737		
lime white	755		
shale blk	762		
lime grey	772		
shale blue	777		
lime grey	817		
shale grey	830		
lime grey	860		