

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location NE cor NW NW.

Sec. 32 T. 22 R. 13E.

Casing Record

County- Greenwood.

20" 10" 965
 15 1/8" 8 1/4" 1380'
 12 1/2" 295 65/8" 1700
 12 1/2" 630 53/16"

Farm- Luthi
 Company- T. K. Simmons et al.
 Contr.- Shull Drlg. Co.
 Comm.- 5/31/1930.

No. 1-B
 Comp.- 6/26/1930.

Total Depth 1880'. Shot 40 Quarts Between 1703-1713'.

Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.

Elevation 1127
 Initial Production Dry.

Date Issued. 7/5/1930.

Formation	Depth	Formation	Depth
soil black	5	lime brown	1090
lime white	45	1 BW 1080-1090	
shale blue	55	lime lgt	1120
lime white	65	shale lgt	1255
shale blue	85	lime lgt	1260
shale lgt	90	shale lgt cave	1275
lime white	100	lime white	1290
shale drk	105	shale lgt	1295
shale lgt	110	lime lgt	1300
red rock	120	shale white	1330
lime gray	130	lime white	1335
shale blue	135	shale white	1355
lime gray	150	lime white	1360
shale gray	160	sand drk	1365
lime gray	190	shale drk	1380
shale lgt	215	Set 8 1/4" csg. 1380'	
lime lgt	225	lime gray	1385
shale gray	250	shale blue	1405
lime gray	255	lime white	1410
shale blue	275	shale lgt	1465
lime lgt	280	shale lgt	1495
shale blue	295	sand lgt 3 BW	1515
Set 15 1/2" csg. 295'		shale drk	1565
shale blue	310	shale lgt	1580
lime lgt	325	shale drk	1640
shale blue	335	shale sdy	1645
lime lgt	360	shale lgt	1703
shale black	365	sand brown oil	1716
lime white	370	shale drk	1770
shale white	380	lime Miss. lgt	1780
lime white	405	lime brown	1840
shale blue	475	lime gray	1880
shale gray	575	HF ^W 1880'	
lime gray	580	Set 6 5/8" csg. 1700'	
sand lgt HF ^W	615	Total Depth	1880'.
shale lgt	630		
shale sdy	660	200' oil in hole before shot.	
shale blue	670	Not enough oil in hole after shot to use swab.	
Set 12 1/2" csg. 630'		All casing pulled out.	
lime gray	680		
shale drk	690		
lime gray	730		
shale white	740		
lime white	785		
shale white	800		
lime white	890		
shale white	895		
lime white 10 BW	945		
shale white	950		
lime white	955		
red rock	965		
Set 10" csg. 965'			
shale blue	1000		