

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION

ST. NW. NE

SEC 32 T 22 R 13 E.

10' 1116 FARM Theophial Le.
20' 8 1-4 1525 COMPANY Skelly Oil Co.
15 1-2 6 5-8 CONTRACTOR
12 1-2 649 5 3-16 COMMENCED

NO. 2 COUNTY Greenwood



TOTAL DEPTH 1766'.

SHOT QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Skelly Oil Company,

El Dorado, Kansas.

ELEVATION 1138

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION Dry.

REMARKS 3/12/27.

Formation	Depth	Formation	Depth
soil black	10	lime gray	1105
lime white	45	lime gray	1125
shale gray	50	shale white	1200
lime white	60	shale brown	1215
shale white	75	lime gray	1225
lime gray	80	shale dark	1275
shale red	90	shale white	1280
lime gray	100	lime gray	1300
shale & lime shells	190	(Cave 1270-1280')	
lime gray	210	slate blue	1350
shale white	230	lime gray	1355
lime gray	235	shale gray	1360
shale brown	290	lime	1375
lime gray	295	(6 BW 1375-1380')	
shale white	310	lime sandy	1380
lime gray	320	shale dark	1400
shale white	330	lime gray	1410
lime gray	360	shale dark	1465
shale & lime shells	425	lime gray	1470
shale white	490	(2 BW 1492 to 1500')	
lime gray	500	shale dark	1492
shale brown	530	sand light	1500
shale light	595	shale blk	1520
sandy lime	600	(Set 8 1/2" at 1575' SLM)	
shale lgt HFW	605	lime gray	1585
sand gray	635	shale dark	1680
shale light	640	shale white	1735
shale gray	680	Little sand at	1692
(12 1/2" 649' SLM)		shale white	1766
shale white	685	Reduced hole at	1687 and
lime gray	765	drilled to 1727, straight reamed 1687	
lime white	845	to 1727 and drilled ahead.	
(HFW 820 to 830')			
lime gray	900	Total Depth SLM	1766'.
shale white	915		
lime gray	945		
shale gray	990		
lime Oswego	1065		
slate blue	1070		
lime sandy gr	1095		
shale dark	1100		
(10" set 1116' SLM)			