

UNION NATIONAL BANK BDLG, WICHITA, KANSAS

Location. CEL NW NW

Sec. ³³ 32 T. 22 R. 11E.


Casing Record.

County Greenwood.

10" 1023 Farm. Wescott
 20" 8" 1666 Company. York State Oil Co.
 15 1/2" 65/8" 1943 Contr. W.F. Braden
 12 1/2" 558 53/16" Conn. 9-30-33

No. 15

Comp. 10-22-33



Total Depth. 2002 Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.

Elevation

Figures Indicate Bottom of Formations.

Initial Production.

Date Issued. 12-2-33

Est 10 bbls.,

Formation	Depth	Formation	Depth.
line	2	shale light	1273
shale light	40	line grey	1281
line grey	65	shale light	1301
shale dark	70	lime light	1415
shale light	90	shale dark	1420
line light	105	lime light	1440
shale light	140	shale shell	1450
line grey	145	shale light	1460
shale light	170	shale grey	1570
line grey	180	lime light	1578 caving.
shale dark	240	shale light	1599
line grey	248	lime grey	1609
shale dark	250	shale dark	1613
lime grey	260	sand grey	1627
shale light	335	shale light	1665
lime light	350	lime brown	1669
shale light	355	shale light	1687
lime light	370	lime brown	1690
shale dark	385	slate dark	1704
lime grey	390	lime light	1708
shale light	420	shale dark	1716
lime light	435	lime grey	1720
shale dark	455	shale light	1775
lime light	460	shale dark	1815
shale dark	465	shale light	1820
lime light	473	lime shell	1824
shale light and lime shells	485	slate light	1843
lime grey	500	shale dark	1875
shale blue	505	shale light	1902
lime grey	518	shale dark	1936
shale light	558	sdv shale	1939
lime grey	575	oil sand brown	1943
shale light	585	1 BO on hour from 1943-1953	
lime light	595	oil sand brown	1953
shale light	633	sand light	1992
lime grey	640	oil sand brown	2000
shale blue	652	shale light	2002 TD.
lime light	680		
shale blk	682	16" conductor 12'	
lime light	695		
shale brown	699		
lime light	717		
shale grey	855		
lime grey	858		
shale light	863		
HFW 863			
sand light	940 HFW		
shale light	955		
lime light	965		
sdv shale	975		
sand light	987		
shale light	990		
shale grey	1010		
lime grey	1027		
lime white	1048		
slate white	1052		
lime white	1062		
shale light	1066		
lime white	1144		
2 BW from 1116-1125			
shale grey	1225		