

34-22-11E

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas

Company - E. C. MURPHY
Farm - CARL HESS No. 2



SEC. 34 T. 22 R. 11E

SW NW NE
325' fr SL, 200' fr
WL NE $\frac{1}{4}$

County. Greenwood

KANSAS

Total Depth. 1885
Comm. 4 -10-50 Comp. 4-24-50
Shot or Treated. Shot 40 qts from 1865-1885
Contractor. Jackman & Jackman
Issued. 9-9-50



CASING:

8 1/4" 41' cem. w/35 sx
5 1/2" 1860' cem. w/50 sx

Elevation. _____

Production. 10 bbls. oil, NW

Figures Indicate Bottom of Formations.

soil	5
lime	30
shale & sholls	300
lime	350
shale, lime, shells	830
water sand	900
sandy shale	990
lime & shale	1050
lime	1445
shale	1863
Bartlesville sand	1880
grey sandy shale	1885
Total depth	

