

16-22-5E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company. E. H. ADAIR OIL COMPANY
Farm. Timmons No. 1

SEC. 16 T. 22 R. 5E
SE SE NE

Total Depth. 2675'
Comm. 7-5-60 Comp. 7-10-60
Shot or Treated.
Contractor. E. H. Adair Oil Co.
Issued. 9-24-60

County Marion
KANSAS



CASING:

8 5/8" @ 166' w/125 sks. cem.

Elevation. 1454' RB

Production. Dry

Figures indicate Bottom of Formations.

lime	26
shale	49
lime	55
shale	75
lime	86
shale	90
lime	143
shale	149
lime	166
shale & lime	1715
lime	1723
shale	1778
lime	1911
shale	1990
lime	2119
shale	2121
lime	2161
shale	2165
lime	2190
shale	2249
lime	2258
lime & shaley lime	2378
shale	2409
lime & shale	2432
Conglomerate	2450
chert	2475
shale & chert	2499
lime	2515
shale	2632
Dolomite, cherty	2655
Dolomite	2675
Total Depth	

<u>TOPS:</u>		<u>SCOUT</u> <u>TOPS</u>
Lansing	1778	1778
Kansas City	1990	1990
Base Kansas City	2190	2190
Cherokee Shale	2378	
Pennsylvania Conglomerate	2430	
Mississippi Chert	2450	2450
Mississippi Limestone	2499	
Kinderhook Shale	2515	2515
Hunton Dolomite	2632	2632
Viola Dolomite	2655	2655