


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. CITIES SERVICE OIL CO.
Farm- Atyeo "C" No. 8

SEC. 6 T. 22 R. 10E
SE NW SE
1650' N & 1650' W of SEc

County Greenwood
KANSAS

Total Depth. 2328
Comm. 1-11-55 Comp. 1-29-55
Shot or Treated. Shot 50 qts. OWE 2293-2328
Contractor. White & Ellis Drilling Co.
Issued. 8-20-55



Elevation. 1375 RB

Production. 46.6 BOPD, NW

CASING:

8 5/8 @ 65.5' w/ 40 sx cmt.
5 1/2 @ 2278' w/ 125 sx cmt.

Figures indicate Bottom of Formations.

clay	4	SIM @ 517, 1003, 1491, 2013, All OK
lime	8	
shale & shells	24	MICT, drld cem. & CO, DD to 2328'
lime	27	FU 200' oil in 10 hrs. shot well,
shale	30	CO to 2328, 355' OIH after CO
lime	39	Swb, 20 1/2 BO/11 hrs.
shale & shells	130	CO to TD.
lime	137	
shale & shells	198	
lime	214	
shale & shells	394	
lime	410	
shale & shells	428	
lime	450	
shale & shells	540	
lime	546	
shale & shells	595	
lime	613	
shale & shells	680	
lime	720	
shale & shells	967	
sandy shale	1070	
shale & shells	1321	
lime	1435	
stickey shale	1553	
lime & shale streaks	1583	
lime	1801	
shale & shells	1898	
lime	1910	
sandy shale	1959	
shale & shells	1983	
lime	1987	
lime & shale streaks	2075	
shale & shells	2115	
sandy shale	2243	
shale & shells	2262	
core #1	2295.5	
core #2	2311	
shale	2312	
sand	2327	
shale	2328	
Total Depth		

TOPS:

Bartlesville section	2260
Bartlesville sand	2283.5
Base Bartlesville sand	2309.5

Best Pay 2283.5-88.5, 2290.5-97 FSO,
2297-2309.5

Core #1 2262-2295.5 rec. 33.5'
Core #2 2297-2311 rec. 14'

All RB Meas.