

26-22-7E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CHARLES L. CARLOCK
Farm- Clark No. 1

SEC. 26 T. 22 R. 7E
SW SW SW

County Chase
KANSAS

Total Depth. 3218'
Comm. 11-13-58 Comp. 11-19-58
Shot or Treated.
Contractor. White & Ellis Drlg. Co.
Issued. 12-27-58



Elevation. 1525' RB

Production. DRY

CASING:
8 5/8" 205' w/150 sx cem.

Figures Indicate Bottom of Formations.

K.B. 5' above G.L.
soil 2
lime 105
shale 115
red rock 120
lime 125
shale 150
red rock 155
lime 165
shale 170
lime 215
shale, shell 385
lime 540
sdy shale, shell 845
lime 925
shale, lime stks 1135
lime 1190
shale, lime 1400
shale 1455
lime 1530
shale 1615
shale, lime stks 1685
shale sdy 1817
lime, Lansing 1946
shale 2083
lime, Kansas City 2255
shale 2355
lime, shale stks 2410
shale, lime 2446
lime 2468
lime, shale stks 2490
shale, lime stks 2590
lime 2599
shale, lime stks 2781
lime, Mississippi 2795
lime 3035
chert 3061
Base lime 3091
lime 3091
shale 3155
shale, Kinderhook 3174
shale, Chattanooga 3194
~~lime, Arbuckle 3218~~
Total Depth

Shale, Kinderhook 3174
Shale, Chattanooga 3194
lime, Arbuckle 3218
Total Depth

TOPS: SCOUT
Heebner 1495
Douglas 1555
Iatan 1705
Lansing 1816
Kansas City 2088
Ft. Scott 2446
Mississippi chat 2781
Mississippi lime 2793
Kinderhook 3091
Chattanooga 3174
Arbuckle 3194