

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
 Union National Bank Bldg, Wichita, Kansas

BARBARA OIL COMPANY.  
 Pixlee No. 15

SEC. 8 T. 22 R. 10E.  
 NWc SW  
 300' fr N & W. lines.


Total Depth. 2323  
 Comm. 9-23-35 Comp. 10-28-35  
 Shot or Treated. 20 qys 2300-2320  
 Contractor. The Shull Drilling Co.  
 Issued. 12-14-35.

County. Greenwood.

CASING.

15 $\frac{1}{2}$ " 372' 65/8" 2268' SIM  
 12 $\frac{1}{2}$ " 865'  
 10" 1390'  
 8 $\frac{1}{2}$ " 1790'

lowered to 1832 UR 1865  
 UR 1910



Elevation.

Production. 90 bbls.

Figures Indicate Bottom of Formations.

shale yellow	10	sand	1290
shale white	40	lime	1300
shale blue	65	shale	1320
lime white	75	lime sdy	1340
shale	100	lime	1375
lime	110	shale	1380
shale	165	lime	1485
lime	170	10" pipe leaking about	500
shale	235	ft off bottom 5 BPHR	
lime	240	shale	1620
shale	265	lime	1645
lime	270	shale	1655
shale	315	lime	1735
lime	320	shale	1740
shale	365	lime	1770
lime	375	shale	1775
shale	380	lime	1790
lime	390	lime	1795
shale	415	Hole full wa ter	1795
lime	430	sand	1820
shale	450	shale	1830
lime	460	shells shale	1840
shale	470	shale	1910
lime	485	lime	1930
shale	525	shale	1935
lime	530	shells and shale	1995
shale	555	shale	2000
lime	575	lime	2010
shale	615	shale	2020
lime	640	lime	2025
shale	700	shale	2030
lime	740	lime	2050
shale	790	shale	2278
lime	810	reduced hole 2267 S.L.M.	
shale	830	shale sdy	2283
HFV 830-855		sand shows oil	2296
sand	855	sand shows oil	2306
lime	860	sand shows oil	2321
shale	890	shale	2323
lime	905	Total Depth.	
shale	920		
lime	930	Hole filled 400 ft while drilling	
shale	935	in. 800 feet oil in hole after	
lime	945	setting 12 hours.	
shale	980		
lime	995	Swabbed natural at rate 2 $\frac{1}{2}$ bbls per hr.	
shale	1005	swabbed 189 bbls 35 hour w.	
lime	1060	November 7th milled all 10" 12 $\frac{1}{2}$ " and 15 $\frac{1}{2}$ " casing.	
shale	1100	left in all 8 $\frac{1}{2}$ " and 65/8	
HFV 1100-30			
sand	1135		
shale	1240		
shale sdy	1255		