

9-22-10E  
*Revised*  
*Miller*

UNION NATIONAL BANK BLDG. WICHITA, KANSAS.

Location NW SW NW SW.

Sec. 9 T. 22 R. 10E.

800' fr N & 150' fr WL SW/4

Casing Record

County- Greenwood.  
 No. 2-B.

JUN 23 1930

10" 1388  
 8 1/4" 1950  
 15 1/2" 348 65/8" 2276 SLM  
 2 1/2" 878 53/16"

Farm- Pixlee  
 Company- Theta Oil Co.  
 Contr.- Shull Drlg. Co.  
 Comm.- 4/28/1930. Comp.-5/23/30

Total Depth 2329'.

Shot 40 Quarts Between 2317-2326'.

Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.

Elevation Initial Production 25 bbls.

Date Issued. 6/21/1930.

Formation	Depth	Formation	Depth
cellar	5	shale lgt	1055
shale lgt	45	lime white	1075
lime lgt	55	shale white	1125
shale drk	75	sand white HF	1160
lime lgt	85	shale lgt	1220
shale lgt	100	lime white	1225
lime lgt	105	shale lgt	1250
shale blue	115	sand white water	1305
lime lgt	125	lime white	1320
shale lgt	180	shale lgt	1340
lime white	185	sand lgt	1350
shale blue	230	shale black cave	1370
shale lgt	245	lime white	1388
lime lgt	250	lime white	1435
shale lgt	275	shale lgt	1440
lime white	280	lime white	1505
shale lgt	345	shale lgt	1630
lime white	348	lime white	1810
lime lgt	350	shale lgt	1840
shale lgt	355	shale drk	1925
lime lgt	375	lime white	1930
lime lgt	390	shale lgt cave	1950
shale lgt	425	lime brown	1970
lime white	440	shale lgt	2015
shale lgt	450	lime white	2020
lime lgt	455	shale drk	2035
shale lgt	465	lime lgt	2040
lime lgt	480	shale lgt	2045
shale black	490	shale drk	2055
lime lgt	495	lime lgt	2075
shale drk	525	shale drk	2090
lime lgt	530	shale lgt	2120
shale lgt	570	shale drk cave	2165
lime lgt	580	lime white	2175
shale lgt	620	shale drk cave	2205
lime lgt	645	shale lgt cave	2265
shale sdy drk	695	shale black	2276
3 BV from 650-675		set 6 5/8" csg. 2276 SLM	
shale lgt	705	shale blk ck	2298
lime brown	740	shale lgt	2317
lime white	750	sand oil	2329
shale lgt	770	T.D.	2329
lime white	775		
shale lgt	795		
shale brown	805		
lime lgt	820		
shale & lime shells	855		
shale brown	865		
lime white	878		
shale & lime shells	956		
shale lgt	1005		
lime white	1015		
shale lgt	1020		
lime white	1050		

300' oil in hole before shot.  
 no water.